



Office of the Executive Engineer
Savar-Keraniganj Wellfield Plant, Dhaka WASA
Bhakurta, Savar, Dhaka.
Section-6

Bill of quantity

Name of the Work: Supply, fitting & fixing of heat shrink kit at different DTW pad-mounted sub-stations under SKWP.						
SL No.	Basis of rate	Description of Item	Unit	Q'ty	Unit price	Total Amount
1	PWD-22 E/M Works 4.24.2.3	HEAT SHRINK K TERMINATION KIT Supply & fixing of heat shrink termination kit, outdoor/indoor use complete with DIN lugs, earth connection hardware & cable reparation kit (indoor & outdoor) at the point of cable termination for 11 KV 3-core PVC-insulated & PVC-sheathed & armored / non-armored cable of the following sizes (Made in GERMANY / USA / UK / FRANCE / JAPAN / ITALY / SWEDEN / SWITZERLAND or equivalent accepted/approved by the Engineer-in-charge.) FOR OUTDOOR USE Size: 3 x 70 mm²	per kit	4	10758.000	43032.000
2	A/R	Supply & installation of PIB Tape. Size: 25mm X 10m.	nos	8	750.000	6000.000
3	A/R	Supply & installation of Plastic Tape. Size: 10mm X 10m.	nos	10	50.000	500.000
Total Taka=						49,532.00
In words: Forty-Nine Thousand Five Hundred and Thirty-Two Taka Only.						


 মোঃ আবুল কালাম আজাদ
 উপসহকারী প্রকৌশলী
 সার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।


 মোঃ সুমন আহমেদ
 সহকারী প্রকৌশলী
 সার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট
 ঢাকা ওয়াসা।


 মোঃ নাফিজ ইমতিয়াজ
 নির্বাহী প্রকৌশলী
 সার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।