

Office of the Executive Engineer
Savar-Keraniganj Wellfield Plant, Dhaka WASA
Bhakurta, Savar, Dhaka.
Section-6
Bill of quantity

Name of the Work: Supply, fitting & fixing of Fuse link, heat shrink kit at IRP#1 mainsub-station under SKWP.						
Price Schedule for Goods PG2-2A						
SL No.	Basis of rate	Description of Item	Unit	Q'ty	Unit price	Total Amount
1	PWD-22 E/M Works 2.1.10.2	Supply of outdoor type 11KV, 50 Hz. 5KA (20 KA) dropout fuse complete with mounting accessories, etc. Made in BANGLADESH / BRAZIL or EU countries. (3 Nos. in a set).	set	1	25154.000	25154.000
2	PWD-22 E/M Works 4.24.2.8	HEAT SHRINK K TERMINATION KIT Supply & fixing of heat shrink termination kit, outdoor/indoor use complete with DIN lugs, earth connection hardware & cable reparation kit (indoor & outdoor) at the point of cable termination for 11 KV 3-core PVC-insulated & PVC-sheathed & armored / non-armored cable of the following sizes (Made in GERMANY / USA / UK / FRANCE / JAPAN / ITALY / SWEDEN / SWITZERLAND or equivalent accepted/approved by the Engineer-in-charge.) FOR OUTDOOR USE Size: 3 x 240 mm²	per kit	1	13335.000	13335.000
3	PWD-22 E/M Works 4.25.8	Supplying and fitting of heat shrink joint kit complete with DIN ferrules & G.I armored case at the point of jointing of cables for 4-core / 1000 V grade PVC insulated & sheathed armored / non-armored cable of the following sizes. Made in GERMANY / JAPAN / USA / UK / FRANCE / JAPAN / ITALY / SWEDEN / SWITZERLAND or accepted/approved by the Engineer-in-charge. FOR OUTDOOR USE Size: 4 x 240 mm²	per kit	1	6832.000	6832.000
4	A/R	Supply & installation of PIB Tape. Size: 25mm X 10m.	nos	4	750.000	3000.000
Sub Total PG2-2A (In Figure) =						48,321.000
Price Schedule for Related Service PG2-2B						
5	PWD-22 E/M Works 2.1.15.1	Installation of HT drop-out fuse/ lightning arrester on a prepared U-channel cross-arm on a single / H-pole with necessary fixing materials complete as per the instructions of the Engineer-in-charge. Drop out fuse.	job	1	1227.000	1227.000
Sub Total PG2-2B (In Figure) =						1,227.000
In Total PG2-2A + PG2-2B (In Figure) =						49,548.000
In words: Forty-Nine Thousand Five Hundred and Forty-Eight Taka Only.						

ms
29.09
2025
মোঃ আবুল কালাম আজাদ
উপ-সহকারী প্রকৌশলী
মাতার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।

সুম
29/09/25
মোঃ সুমন আহমেদ
সহকারী প্রকৌশলী
মাতার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট
ঢাকা ওয়াসা।

নাজিম
29/09/25
মোঃ নাজিম ইমতিয়াজ
নির্বাহী প্রকৌশলী
মাতার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।