

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer
Civil Maintenance Division
Dhaka WASA, Dhaka
6th floor, WASA Bhaban
98 Kazi Nazrul Islam avenue, Dhaka.



Name of the Work: Repair and maintenance work at different units (Unit-A7 & B1) of Asad Avenue officers apartment, Dhaka WASA.

Sl. No.	Item No.	Description of the item	Quantity	Unit	Rate	Amount
1	PWD-22 14.13	Supplying fitting and fixing of aluminium fixed fan light as per the U.S. Architectural Aluminium Manufacturer's Association (AAMA) standard specification and BDS 1879:2014 having minimum 1.2 mm thick fixed bottom (size 76.2 mm, 38.10 mm, 0.640 kg/m), minimum 1.2 mm thick (17.40 mm, 31.78 mm bottom cover 0.250 kg/m) and minimum 1.2 mm thick groove cover (size 57.15mm, 15.80 mm, 0.362 kg/m) and minimum 1.2 mm thick top and side section (76.20 mm, 16 mm, 38.10 mm, 0.769 kg/m) fixed with above mentioned frames and all aluminium members will be anodized to aluminium bronze/silver/ss/black colour with a coat not less than 15 microns in thickness or powder coated to any colour with a coat not less than 25 microns in thickness and density of 4 mg per square cm etc. including all accessories, neoprene sealant, nut and bolt etc. complete in all respect as per				
	14.13.2	Powder coated to any colour	4.180	sqm	6377.000	26655.860
2	PWD-22 16.2.1	Interior standard acrylic emulsion paint (plastic or matt finish) of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container; applying to interior wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary interior sealer of specified brand on prepared surface; then applying necessary interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of interior emulsion paint spreading by brush/roller/spray &	90.000	Sqm	258.000	23220.000
					Total : TK.	49875.860
					Say Total : TK.	49876.000

In word: Forty nine thousand eight hundred seventy six taka only

26/09/2025

মোহাম্মদ রিয়াজুল ইসলাম
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

23.09.25
রাহাত উন নবী
সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

23.09.25
মুজা সাহা
নির্বাহী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।