

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer

Civil Maintenance Division

Dhaka WASA, Dhaka

6th floor, WASA Bhaban


98 Kazi Nazrul Islam avenue, Dhaka.


Name of the Work: Repairing lift core and ancillary maintenance works of different quarter at Dhakeshwari officers apartment, Dhaka WASA.

Sl. No.	Item No.	Description of the item	Quantity	Unit	Rate	Amount
1	PWD-22 3.6	Damp proof course (DPC) (1:1.5:3) of cement concrete with cement, sand and picked jhama brick chips or stone chips including breaking of chips, screening, centering, shuttering, casting, curing and finishing with a coat of bitumen including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM.II/B.M)				
	3.6.1	75 mm thick damp proof course (1:1.5:3) with cement, Sylhet sand (F.M. 2.2) and stone chips.	9.850	sqm	1528.420	15054.937
2	PWD-22 26.10	Supplying, fitting and fixing of flush valve for water closet on walls or directly over water closet with necessary accessories, making holes wherever required and mending good the damages and fitting, fixing & finishing etc. all complete with all necessary fittings and connections approved and accepted by the Engineer-in-charge.				
	26.10.1	Flush valve (local)	2.000	each	14638.420	29276.840
3	M/R	Repairing of 10 KW submersible pump motor	1.000	each	5500.000	5500.000
					Total : TK.	49831.777
					Say Total : TK.	49832.000

In word: Forty nine thousand eight hundred thirty two taka only


22/09/2020
মোহাম্মদ রিয়াজুল ইসলাম
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।


21.09.25
রাহাত উন নবী
সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।


22/09/2020
মুজা সাহা
নির্বাহী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।