

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY


Office of the Executive Engineer
Civil Maintenance Division
Dhaka WASA, Dhaka
6th floor, WASA Bhaban
98 Kazi Nazrul Islam avenue, Dhaka.


Name of the Work: Supplying, fitting & fixing letter box for central receive pool & partition wall for office of the Administration-02 of Dhaka WASA.

Sl. No.	Item No.	Description of the item	Quantity	Unit	Rate	Amount
1	PWD-22 18.2.1	Supplying, fitting and fixing 12 mm thick burma teak (BT) veneered board/ ply board/ particle board in walling with best quality and well seasoned garjan wood frame of section of 50 mm x 25 mm at 600 mm x 600 mm in grid, including grove where necessary, fitted and fixed to wall by plugs, nails, screws etc. maintaining leveled and finished exposed faces including. making holes in wall and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, electricity, accessories, labour for installation, scaffolding, screws, nails etc. All complete as per design, approved sample and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-				
	18.2.1.2	12 mm thick BT ply board walling	2.091	sqm	3098.100	6478.127
2	PWD-22 18.6.1	Supplying, fitting and fixing Wall Almirah with one side attires cabinet including locker and another side shelf of Depth-1'-8" made by 18 mm B.T Veneered/ B.T. ply/ B.T marine ply board on 2.50"x2.50" (Finished) Ctg. Teak Wooden Outer Frame, 1.50" x 1.50" (Finished) Ctg. Teak wooden frame for shelf, 1.25" x 1.25" (Finished) Ctg. Teak wooden edge bit around the shutter, backside covered by the 18mm garjan Ply board, 2 nos standard handle for shutter & 3 nos standard lock for shutter and drawer, 25mm SS pipe 1.5 mm thick and including all necessary accessories for fitting & fixing all complete and accepted by the engineer-in-charge. All Ctg. teak wood frames must be protected from termites, cockroach and other insects. (Rate is excluding cost of polish/ paint etc. of any type).				
	18.6.1.1	Wall Almirah with one side attire cabinet including locker and another side shelf made of 18 mm B.T Veneered board	1.620	sqm	18300.000	29646.000
3	M/R	Supplying, fitting & fixing grill box for CBA Room	1.00	item	13500.000	13500.000
					Total : TK.	49624.127
					Say Total : TK.	49624.000

In word: Forty nine thousand six hundred twenty four taka only


 28/07
 2025
 মোহাম্মদ রিয়াজুল ইসলাম
 উপ-সহকারী প্রকৌশলী
 সি এম বিভাগ
 ঢাকা ওয়াসা।


 24.09.25
 রাহাতুন উন নবী
 সহকারী প্রকৌশলী
 সি এম বিভাগ
 ঢাকা ওয়াসা।


 24.09.25
 মুক্তা সাহা
 নির্বাহী প্রকৌশলী
 সি এম বিভাগ
 ঢাকা ওয়াসা।