

HOSSAIN BROTHERS & ENGINEERING WORKS

Price and Delivery Schedule for Goods (Form e-PG2-2A)

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	The Following Items shall be supplied to the Padma Water Treatment Plant sub-store. Supplied Items shall be accepted after joint inspection by SE (WSTPC), EE P&D (E&M) Division and Concerned Division. Warranty period of all the Items shall be 06 (six) months from the date of final acceptance, if any fault occurs during the Warranty period the tenderer will be responsible for replacing or repairing the same at their own cost. Prices are inclusive of all Taxes, VAT etc. "Supply and installation of Sprinkler with RCC-Base Work: A. Sprinkler base: 18" hight, 12" bottom & 6" top square shape base containing 2" inlet side to side and 1"/1.5" delivery line on top. Footing: for 1" pipe. B. Sprinkler	set	60.000	Padma Water Treatment Plant	90	Bangladesh	32776.001	Thirty-Two Thousand Seven Hundred and Seventy-Six point Zero Zero One	1966560.060	Nineteen Lakh Sixty-Six Thousand Five Hundred and Sixty point Zero Six

	(composite materials & 30 feet diameter spray coverage range). for large scale Sprinkler (UPVC/ Polycarbonic material) & 15 feet diameter spray coverage range for medium scale. C. SS Running pipe (6"X2) D. GI running pipe 1 feet (1") E. Socket 1" to 3/4" F. Socket 1" to 1" G. Ball Valve 1" to 1" Footing: for 2" pipe. H. Running pipe 2 feet with both side thread cutting Socket 2"- in/out & 1" delivery. (all complete as per direction and approval of the engineer in charge.)"									
2	Supply of best quality standard size plastic/rubber hose pipe 1" dia as per direction and approval of the engineer in charge.	m	520.000	Do	90	Bangladesh	130.001	One Hundred and Thirty point Zero Zero One	67600.520	Sixty-Seven Thousand Six Hundred point Five Two
								Grand Total:	2034160.580	Twenty Lakh Thirty-Four Thousand One Hundred and Sixty point Five Eight

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md. Hossan on behalf of HOSSAIN BROTHERS & ENGINEERING WORKS

HOSSAIN BROTHERS & ENGINEERING WORKS

Price and Completion Schedule for Related Services (Form e- PG2-2B)

Price and Completion Schedule for Related Services

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Earth Work: A. 18" wide and 24" deep, channel excavation for pipeline installation. 1.5 ft X 2 ft X 800 ft= 2400 cft B. After every 30 feet there will be a connection box- excavation 24" X 24" for sprinkler base. 2 ft X 2 ft X 2 ft = 8 cft X 60 nos= 480 cft C. Channel excavation will be done in manual process through regular worker."	cft	2880.000	Padma Water Treatment Plant	90	Bangladesh	25.001	Twenty-Five point Zero Zero One	72002.880	Seventy-Two Thousand AND Two point Eight Eight
2	"Pipeline: A. Pipeline length 800 feet & 15% for footing wastage"	ft	920.000	Do	90	Bangladesh	155.001	One Hundred and Fifty-Five point Zero Zero One	142600.920	One Lakh Forty-Two Thousand Six Hundred point Nine Two
3	B. Bottom lining will be 2" UPVC lining with GI footing (union) 5% for footing wastage.	ft	96.000	Do	90	Bangladesh	120.001	One Hundred and Twenty point Zero Zero One	11520.096	Eleven Thousand Five Hundred and Twenty point Zero Nine Six
4	Drilling for connection from service water manhole and reconstruction of connection pit.	nos	4.000	Do	90	Bangladesh	12000.001	Twelve Thousand point Zero Zero One	48000.004	Forty-Eight Thousand point Zero Zero Four
5	Sprinkler Installation Charge.	nos	60.000	Do	90	Bangladesh	2200.001	Two Thousand Two Hundred point Zero Zero One	132000.060	One Lakh Thirty-Two Thousand point Zero Six
6	Pressure Test:	item	1.000	Do	90	Bangladesh	18990.001	Eighteen Thousand	18990.001	Eighteen Thousand

Pressure testing at minimum 6.5 bar and maximum 10 bar after completion of the work to ensure adequate pressure in the network all complete as per direction of the engineer in charge.								Nine Hundred and Ninety point Zero Zero One	Nine Hundred and Ninety point Zero Zero One
								Grand Total:	425113.961 Four Lakh Twenty-Five Thousand One Hundred and Thirteen point Nine Six One

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md. Hossan on behalf of HOSSAIN BROTHERS & ENGINEERING WORKS