


**Office of the Executive Engineer**

MODS Zone-6, Dhaka WASA  
Fakirapool Water Tank Compound  
Motijheel, Dhaka.

Name Of the Work : Removing blockage, Cleaning of sewer line & removing lifted soil from manhole at Chamelibagh (35 Chamelibagh) and adjunct area under MODS Zone-6, Dhaka WASA.

| Item No | Basis of Rate | Group | Description of the items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Unit | Qty    | Unit rate (Tk.) | Amount (Tk.) |
|---------|---------------|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|-----------------|--------------|
| 1       | 2             | 3     | 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 5    | 6      | 7               | 8 =(5*7)     |
| 1.00    | Approved Rate | Civil | Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also covers clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge | Sqm. | 12.000 | 169.001         | 2,028.012    |



| Item No | Basis of Rate | Group | Description of the items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Unit | Qty    | Unit rate (Tk.) | Amount (Tk.)      |
|---------|---------------|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|-----------------|-------------------|
| 2.00    | Approved Rate | Civil | Earth work in excavation in all kinds of soil for foundation trenches including layout, providing enter lines, local bench- mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract.                                                                                     | Cum  | 0.600  | 1,212.001       | <b>727.201</b>    |
| 3.00    | Approved Rate | Civil | Removing sludge or semi-liquid clay/substances etc. not suitable for pumping out or carrying by head load from the bottom of any marshy land, lake, ditch, pond by mixing fine local sand of minimum F.M. 0.8 to a proportion such that it can be carried to an intermediate point of disposal and cutting the same including stacking and spreading properly on a suitable place to dry in the sun for a certain days and dispose the dried sludge or clay to a safe distance etc. complete and accepted by Engineer-in-charge subject to submit method statement to the engineer in charge for carrying out the works including ultimate disposal of the sludge under this item for approval. However, engineer's approval shall not relieve the Contractor of his responsibilities and obligations under the contract. | Cum  | 11.304 | 1,054.001       | <b>11,914.427</b> |
| 4.00    | Approved Rate | Civil | Cleaning and disposing of excavated earth from the construction site by truck or by any other means to a place within 30 km radius of the city or town area including loading & unloading at both ends, leveling and dressing the carried earth etc. complete and accepted by the Engineer-in-charge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | P/nr | 11.304 | 756.001         | <b>8,545.835</b>  |


*S. Ande*

*[Signature]*


*[Signature]*

| Item No                 | Basis of Rate                 | Group | Description of the items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit | Qty     | Unit rate (Tk.) | Amount (Tk.)      |
|-------------------------|-------------------------------|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------|-----------------|-------------------|
| 5.00                    | C-02.19.1, PWD-2022           | Civil | Bailing out water by 1 cusec diesel operated pump including hire charge of pump, fuel, operator, spares and maintenance etc. all complete and accepted by the Engineer-in-charge                                                                                                                                                                                                                                                                                                                                                | hr   | 24.000  | 677.001         | 16,248.024        |
| 6.00                    | C24-Missl.item-1959, PWD-2022 | Civil | Empty gunny bags/ Polymer bag to fill sand for load test                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | each | 200.000 | 20.000          | 4,000.000         |
| 7.00                    | Approved Rate                 | Civil | Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and othercharges etc. all complete and accepted bye engineer-in-charge. (Cement: CEM-II / B-M)                                                                                                                                | Cum  | 0.096   | 10,504.001      | 1,008.384         |
| 8.00                    | C-4.3, PWD-2022               | Civil | Brick works with first class bricks with cement sand (F.M.1.2) mortar (1:4) in exterior walls including filling the interstices with mortar, raking out joints, cleaning and socking the bricks at least for 24 hours before use and washing of sand,necessary scaffolding, curing at least for 7 days etc. all complete including cost of water, electricity and other charges (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) accepted by the Engineer-in-charge | Cum  | 0.065   | 10,097.001      | 653.907           |
| 9.00                    | C-32.88, PWD-2022             | Civil | Clearing sludges & night soil from Inspection pit (Service pit)                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | each | 6.000   | 525.001         | 3,150.006         |
| <b>Total Amount Tk.</b> |                               |       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |         |                 | <b>48,275.796</b> |
|                         |                               |       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |         |                 | <b>48,275.796</b> |

(In word :Taka Fourty Eight Thosand Two Hundred Seventy Five point seven nine six paisa only)

  
 Sub-Assistant Engineer  
 MODS Zone-6,  
 Dhaka Wasa

  
 Assistant Engineer  
 MODS Zone-6,  
 Dhaka Wasa

  
 Executive Engineer  
 MODS Zone-6,  
 Dhaka Wasa