

M/s. Active International

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	APPROVED RATE	Cleaning of (1) two manual screen (east and west side) installed before twin box culvert at Mridhabari (2) Net- bamboo fencing installed before manual screen (3) Net- bamboo fencing installed at acration zone-1 of DND canal by skilled divers. The screen and acration zone-1 net-bamboo are installed to separate floating debris like polythene, coconut shell, cloth, different types of plants etc from raw water. The divers will be well equipped with SCBA (Self contained breathing apparatus) and any other equipment necessary for working under water. Cleaning of five points as mentioned above will be treated as one item.	Item	1.000	40049.983	Forty Thousand And Forty-Nine Point Nine Eight Three	40049.983	Forty Thousand And Forty-Nine Point Nine Eight Three	I have seen
2	N/A	APPROVED RATE	Fitting Fixing Nylon rope net (Mesh size-50mm x 50mm, Rope dia size-2.5mm-3mm) with installed bamboo support before Mridhabari and aeration zone-1. All cost including net, wire, labour charge and any other expenditure related with this will be carried by the contractor. The bill will be provided according to the actual amount of net used.	sqm	105.000	324.001	Three Hundred And Twenty-Four Point Zero Zero One	34020.105	Thirty-Four Thousand And Twenty Point One Zero Five	I have seen
3	N/A	APPROVED RATE	Installation of 3-4 inch dia Barak bamboo (Length 35 ft each) vertically, horizontally and inclined position to net bamboo fencing installed before Mridhabari and aeration zone-1. All costs including bamboo, rope, wire nail, labour, diver and any other expenditure related with this will be carried by the contractor. The bill will be provided according to the actual amount of bamboo used	nos	48.000	810.001	Eight Hundred And Ten Point Zero Zero One	38880.048	Thirty-Eight Thousand Eight Hundred And Eighty Point Zero Four Eight	I have seen
4	N/A	APPROVED RATE	Special type labour for removing, cleaning of old net with bamboo clogged from water hyacinth and floating debris in Aeration zone-1. Also the labour will be employed for trimmimg, maintenance and adjustment of floating wetland (Kolabati, phragmites) installed for removal of ammonia and other pollutants in DND canal	Man-day	465.000	810.001	Eight Hundred And Ten Point Zero Zero One	376650.465	Three Lakh Seventy-Six Thousand Six Hundred And Fifty Point Four Six Five	I have seen
							Grand Total:	489600.601	Four Lakh Eighty-Nine Thousand Six Hundred Point Six Zero One	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Syed Zahid on behalf of M/s. Active International

M/s. Active International

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
489600.601	-5.000	465120.570	Four Lakh Sixty-Five Thousand One Hundred And Twenty Point Five Seven
	Grand Total:	465120.570	Four Lakh Sixty-Five Thousand One Hundred And Twenty Point Five Seven

This Tenderer's Quoted Price is Electronically Signed by Mr. Syed Zahid on behalf of M/s. Active International