

Office of the Executive Engineer
Store Division, Dhaka WASA.

Name of the Work: Estimate for Repair and maintenance of Parapet Wall and Short RCC Column at 1st floor of Office Building at Store Division, Dhaka WASA .

Sl. No.	Group	Rate schedule item No.	Description of Item	Unit	Qty	Rate (Tk)	Amount (Tk)
1	2	3	4	5	6	7	8
1	Civil	PWD-1.7	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also covers clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	Sqm	952.000	218.001	207536.952
2	Civil	PWD-2022: 32.1	Stripping of unserviceable plaster including racking out joints, cleaning etc.	Sqm	1064.000	31.001	32985.064
3	Civil	PWD 15.3	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to dado with cement (1:4) up to 150 mm including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	Sqm	1064.000	373.001	396873.064
4	Civil	PWD-16.1.2	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer (Berger Weather Coat Antidirt Long Life/ Elite Master Coat/ Asian Apex Ultima or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading	Sqm	1064.000	298.001	317073.064
5		LS	Site Cleaning	Item	1.000	2068.808	2068.808
						Total Tk.	749000.000

In word TK. (Seven Lac Forty Nine Thousand) Taka Only.


18/09/25
MD. RAIHAN ALI
Sub-Assistant Engineer
Store Division, Dhaka WASA.


18/09/25
PAUL SARKER
Assistant Engineer
Store Division, Dhaka WASA


18/09/25
সৈয়দ শিহাবুর রহমান
নির্বাহী প্রকৌশলী (অ: দা:)
ভান্ডার বিভাগ, ঢাকা ওয়াসা।