

M/S SHARIF TRADERS


Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	3.1	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks including preparation of bed and filling the interstices with local sand, levelling etc. complete and accepted by the Engineer-in-charge	Sqm	33.488	420.001	Four Hundred And Twenty Point Zero Zero One	14064.993	Fourteen Thousand And Sixty-Four Point Nine Nine Three	I have seen
2	Civil	3.4.1	Mass concrete (1:3:6) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) Mass concrete in foundation (1:3:6) with cement, brick chips and sand of F.M. 1.2	Cum	3.790	10500.001	Ten Thousand Five Hundred Point Zero Zero One	39795.003	Thirty-Nine Thousand Seven Hundred And Ninety-Five Point Zero Zero Three	I have seen
3	Civil	3.7	Supplying and laying of single layer polythene sheet weighing one kilogram per 6.5 square meter in floor or anywhere below cement concrete complete in all respect and accepted by Engineer-in-charge.	Sqm	38.372	42.001	Forty-Two Point Zero Zero One	1611.662	One Thousand Six Hundred And Eleven Point Six Six Two	I have seen
4	Civil	1.10.1	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified	Cum	14.185	3257.001	Three Thousand Two Hundred And Fifty-Seven Point Zero Zero One	46200.559	Forty-Six Thousand Two Hundred Point Five Five Nine	I have seen

			proctor test) by ramming each layer u							
5	Civil	17.40	Average 100 mm thick finished lime terracing with 20 mm down graded first class brick chips (khoa), surki from 1st class bricks and minimum lime content 500 kg per 2.83 cubic meter (stone lime brought at site, not being powdered in open air and to be slaked in presence of engineer-in-charge and to be measured in volume three days after slaking for using in the mix) in the proportion 7:2:2 (brick chips : surki : lime) including preparation of the mix on the ground by making a suitable platform under proper polythene cover. Cutting the mix twice daily with limewater (1:10) at least for 7 days until the mix attain desirable consistency. Laying the mix in proper slope, beating the same with standard ?koppa? for minimum 7 days to gain maximum consolidation, making ghoondy and neat finishing with lime Surki mortar (1:2) and curing for 21 days providing polythene cover after each day work and cleaning etc. complete in all respect accepted by the Engineer-in-charge. Ist Floor	Cum	2.551	13165.001	Thirteen Thousand One Hundred And Sixty- Five Point Zero Zero One	33583.917	Thirty- Three Thousand Five Hundred And Eighty- Three Point Nine One Seven	I have seen

সত্যায়িত

 মোঃ মেহেদ হাসান
 সহকারী প্রকৌশলী
 মডুস জোন-১, ঢাকা ওয়াশা

manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in 2 coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.

Zero Zero One

Eight Point Six One Eight

8	Civil	26.52.2	Supplying, fitting and fixing of best quality faucets etc. complete approved and accepted by the Engineer-in-charge. 12 mm special quality CP bib cock	Nos	1.000	1106.461	One Thousand One Hundred And Six Point Four Six One	1106.461	One Thousand One Hundred And Six Point Four Six One	I have seen
9	Elec	18.1.1(i)	CEILING FAN Supplying & fixing AC capacitor type ceiling fan of following sizes complete with min. 3048 mm. (1 ft) long down rod, blades, capacitor canopy, regulator etc. connecting PVC wire complete as required:- a) 1422.4 mm. (56") Sweep BRB Super Deluxe /Citizen super Deluxe/Jamuna Super Deluxe/Prime super Deluxe/Prodip Super Deluxe/RK Deluxe/or equivalent approved by the Engineering-in-Charge.	Each	1.000	4047.462	Four Thousand And Forty-Seven Point Four Six Two	4047.462	Four Thousand And Forty-Seven Point Four Six Two	I have seen
10	Civil	16.13	Colour wash with yellow orchard/any other colour pigment by two coats over a prime coat of white wash, lime mixture prepared at least 12 hours before use, slacking stone lime, supply of gums, blue, stirring thoroughly, removing the floating materials from the mixer, surface cleaning to free from all foreign materials before application of each coat, applying one vertical and one horizontal wash for each coat and successive coat is to be applied after drying up of previous coat including	Sqm	573.023	25.001	Twenty-Five Point Zero Zero One	14326.148	Fourteen Thousand Three Hundred And Twenty-Six Point One Four Eight	I have seen

			hair brass, providing necessary scaffolding and cleaning plinth, floors, doors, windows, portions and ventilators by washing, rubbing, oiling if necessary after white wash for all floors including cost of water, electricity and other charges etc. complete in all respect in all floors and accepted by the Engineer.							
11	Civil	16.11	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling in 2 coats over a coat of brand specified primer or sealer elapsing specified time for drying/ recoating matt finish including cleaning and sand papering making the surface free from loose and flaky materials, dirt, grease, wax, polish, scraping all chalked and scaled materials, applying the paint by brush/roller and necessary scaffolding etc. all complete in all floors accepted by the Engineer.	Sqm	166.949	196.001	One Hundred And Ninety-Six Point Zero Zero One	32722.170	Thirty-Two Thousand Seven Hundred And Twenty-Two Point One Seven	I have seen
Grand Total:								249766.931	Two Lakh Forty-Nine Thousand Seven Hundred And Sixty-Six Point Nine Three One	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md Uddin on behalf of M/S SHARIF TRADERS

সত্যায়িত
 30/12/25
 মোঃ মেহেদী হাসান
 সহকারী প্রকৌশলী
 মডুস জোন-১, ঢাকা ওয়াসা

M/S SHARIF TRADERS

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
249766.931	-5.000	237278.584	Two Lakh Thirty-Seven Thousand Two Hundred And Seventy-Eight Point Five Eight Four
	Grand Total:	237278.584	Two Lakh Thirty-Seven Thousand Two Hundred And Seventy-Eight Point Five Eight Four

This Tenderer's Quoted Price is Electronically Signed by Mr. Md Uddin on behalf of M/S SHARIF TRADERS

সত্যায়িত
 20/12/25
 মেঃ মেহেদী হাসান
 সহকারী প্রকৌশলী
 মডুস জোন-১, ঢাকা ওয়াশা