

MAA ENTERPRISE AND ENGINEERING WORKS

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	APPROVED RATE	Stripping of unserviceable plaster including racking out joints, cleaning etc.	sqm	360.000	31.001	Thirty-One Point Zero Zero One	11160.360	Eleven Thousand One Hundred And Sixty Point Three Six	I have seen
2	N/A	APPROVED RATE	Premium synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in two coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	sqm	180.000	238.000	Two Hundred And Thirty-Eight	42840.000	Forty-Two Thousand Eight Hundred And Forty	I have seen
3	N/A	APPROVED RATE	Solvent based water repellent of approved quality delivered from authorized local agent of the manufacturer in a sealed container; surface preparation including cleaning, drying, making free	sqm	180.000	452.000	Four Hundred And Fifty-Two	81360.000	Eighty-One Thousand Three Hundred And Sixty	I have seen

			from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 3 coats of silicon based water repellent on exposed brick surface/fair face surface spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge							
4	N/A	APPROVED RATE	"Repairing of 2(two) nos. Aluminium sulphate & Lime solution mixing tank floor by the following procedure. 1) Stripping of unserviceable piaster & glass fiber Including racking out joints, cleaning etc. 11) Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to dado with cement (1:4) up to 150 mm including washing of sand, finishing the edges and comers and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-Incharge. III) After completed cement plastering It will take on installed by the glass fiber OS(Five) layer coating. Material specification: Epoxy Resin (Acid Proof)	sft	360.000	998.000	Nine Hundred And Ninety-Eight	359280.000	Three Lakh Fifty-Nine Thousand Two Hundred And Eighty	I have seen

			Fiber glass: 300 gram per square meter(or 10.764 sqft) Total thickness after work will be 3. Smm"" In"							
								Grand Total:	494640.360	Four Lakh Ninety- Four Thousand Six Hundred And Forty Point Three Six

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Mohammad Gazi on behalf of MAA ENTERPRISE AND ENGINEERING WORKS

MAA ENTERPRISE AND ENGINEERING WORKS			
Tenderer's Quoted Price			
Tenderer's Quoted Price			
Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
494640.360	-5.000	469908.342	Four Lakh Sixty-Nine Thousand Nine Hundred And Eight Point Three Four Two
	Grand Total:	469908.342	Four Lakh Sixty-Nine Thousand Nine Hundred And Eight Point Three Four Two

This Tenderer's Quoted Price is Electronically Signed by Mr. Mohammad Gazi on behalf of MAA ENTERPRISE AND ENGINEERING WORKS