



**Office of The Executive Engineer
PSTP Division, Dhaka WASA.**


Subject: Supply of panaflex sticker, signboard and other necessary items for PSTP.


SI No	Description of Items	Unit	Quantity	Unit Rate	Amount
1	Supplying, fitting and fixing MS sign board (8 feet x 6 feet) as per design and technical specification. All complete and approved by the Engineer.	Each	3	48000	144000
2	Supplying, fitting and fixing MS sign board (6 feet x 4 feet) as per design and technical specification. All complete and approved by the Engineer.	Each	2	45000	90000
3	Supplying, fitting and fixing 8 feet x 6 feet panaflex peasting on MS sign board as per design and and technical specification. All complete and approved by the Engineer.	each	14	7000.000	98000.00
4	Supplying, fitting and fixing 6 feet x 4 feet panaflex peasting on MS sign board as per design and and technical specification. All complete and approved by the Engineer.	nos	14	5000	70000
5	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead.	cum	17.01	168.001	2857.697
6	FORMWORK (Wooden) for boundary wall, gate, centry post etc. Pedestals, column, wall	sqm	33.43	526.001	17584.213
7	Grade 400 (B400DWR / B420DWR: complying BDS ISO 6935-2:2016 / ASTM A615) ribbed or deformed bar produced and marked according to Bangladesh standard, with minimum yield strength, fy (ReH)= 400 MPa but fy not exceeding 480 MPa and whatever is the actual yield strength within allowable limit as per BNBC/ ACI 318, the ratio of ultimate tensile strength fu to yield strength fy, shall be at least 1.25 and minimum elongation after fracture and minimum total elongation at maximum force is 17% and 8% respectively ; up to ground floor.	kg	188.45	121.001	22802.638


SI No	Description of Items	Unit	Quantity	Unit Rate	Amount
8	Reinforced cement concrete works with minimum cement content relates to mix ratio 1:2:4 having maximum water cement ratio = 0.40 and minimum f_{cr} = 30.5 MPa, satisfying a specified compressive strength f_c = 22 MPa at 28 days on standard cylinders as per standard practice of Code ACI/BNBC/ASTM, cement conforming to BDS EN-197-1-CEM-I, 52.5N (52.5 MPa) / ASTM-C 150 Type - I, best quality Sylhet sand or coarse sand of equivalent F.M. 2.2 and 20 mm down well graded stone chips conforming to ASTM C-33 (Aggregate grading as per table shown in technical specification), conducting necessary tests, making and placing shutter in position maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing in standard mixer machine with hopper fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering after specified time approved; including cost of water, electricity, other charges etc. all complete, approved and accepted by the Engineer-in-charge. (Rate is excluding laboratory test fees, the cost of reinforcement and its fabrication, placing, binding etc. and the cost of shuttering & centering). Pedestals, column, column capital, lift wall and RCC wall up to ground floor	cum	3.4430	13863.001	47730.312
9	Site cleaning, providing safety facilities etc as per direction of the Engineer	LS	1	3700	3700.000
Total Taka					496674.84

Taka In word : Four Lac Ninety Six Thousand Six Hundred Seventy Four Point Eight Four Only.


Sub-Assistant Engineer
 PSTP Division, Dhaka WASA.


 24.09.2025
Sub-Divisional Engineer
 PSTP Division, Dhaka WASA.


Executive Engineer
 PSTP Division, Dhaka WASA.