

Office of the Executive Engineer
Store Division, Dhaka WASA.

Name of the Work: Repairing, Maintenance and Cleaning of Surface drain at Store Division Compound, Dhaka WASA.

Sl. No.	Rate schedule item No.	Description of Item	Qty.	Unit	Rate (Tk)	Amount (Tk)	
1	2	3	4	5	6	7	
1	PWD-2022: 1.7	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also covers clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	900.000	Sqm	P/sqm	218.001	196200.900
2	PWD-2022: 32.77	Labour charge for cleaning, washing, brooming from all heights and stacking of debris at a place beyond plinth area of the the site during execution of repair works as per direction of the engineer-in-charge	90.00	Cum	P/cum	1451.001	130590.090
3	PWD-32.83	Cleaning, renewing of drain and apron with cement concrete or cement mortar etc as per direction of Engineer-in-charge.	90.00	m	P/m	232.001	20880.090
4		Construction of masonry inspection pit with 250 mm thick brick work in cement mortar (1:4) including necessary earth work, side filling and one layer brick flat soling, 75 mm thick (1:3:6) base concrete for making invert channel and 12 mm thick (1:2) cement plaster with neat finishing etc. all complete up to a depth of 700 mm approved and accepted by the Engineer- in- charge.					
	PWD-26.72.3	Clear 600 x 600 mm and depth 750 mm to 900 mm, average 825 mm for single 300 mm dia R.C.C. pipes and 400 mm PVC pipe.	11.00	each	P/each	10699.001	117689.011
5		Construction and placing of R.C.C inspection pit cover (slab) with supplying and provisions for placing, fitting, fixing 450 mm dia C.I. man-hole cover with locking/unlocking arrangement including concrete (1:2:4) with approx. 1% re-enforcement, necessary earth cutting, or cleaning, side filling, curing etc. with minimum 12 mm cement plaster (1:4) and neat cement finishing on edges and top all complete and accepted by the Engineer- in-charge.					

D/A 




Sl. No.	Rate schedule item No.	Description of Item	Qty.	Unit	Rate (Tk)	Amount (Tk)
1	2	3	4	5	6	7
	PWD-26.73.3	Clear 600 mm x 600 mm and depth 750 mm to 900 mm, average 825 mm for single 300 mm dia R.C.C. pipes and 375 mm and 400 mm PVC pipe with pit cover and 450 mm dia C.I. man-hole cover.	11.00 each	P/each	2440.001	26840.011
6	L.S.	Site Cleaning as per direction of the Engineer in charge.	1.00 Item	P/Item	6399.898	6399.898

Total Tk. 498600.000

In word TK. (Four lac Ninety Eight Thousand Six Hundred) Only.


 Sub-Assistant Engineer
 Store Division
 Dhaka WASA


 Assistant Engineer
 Store Division
 Dhaka WASA


 Executive Engineer
 Store Division
 Dhaka WASA

Superintending Engineer
 SMWC Circle
 Dhaka WASA