


Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.


Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front Of Aftab Nagar Steel Bridge (DMA-806) under MODS Zone-8, Dhaka WASA .

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	7.00	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Sleeve E.F	2	Nos	5000.00	10,000.00	
3	Approved Rate	Excavation and removal of soft soil (on written permission of E/C) from the trench bottom beyond allowable depth and back fill of this by supplying, depositing and compaction in 150 mm layer of fine sand (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, (3.50*4.40*1.52)= 23.408 cum	23.41	Cum	331.00	7748.05	
4	Approved Rate	supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters. (3.50*4.40*1.52)= 23.408	23.41	Cum	578.00	13530.98	
5	Approved Rate	Mechanics Charge	2	P/Person	1000.00	2000.00	
6	Approved Rate	Daily Labour	15	P/Person	800.00	12000.00	
7	Approved Rate	Hire charge of de-watering pump	2	P/Day	2141.30	4282.60	
Total						49561.63	

In words: Forty Nine Thousand Five Hundred & Sixty One Point Six Three Taka Only.


17.01.24
আবুল কালাম আল মনির
উপ-সহকারী প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াসা।


17.01.24
মোঃ মোতবার
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা


29/01/2024
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।