

R M Construction

Bill of Quantities

Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
1	N/A	N/A	Stripping of unserviceable plaster, cleaning etc.	sqm	136.960	500.000	Five Hundred	68480.000	Sixty-Eight Thousand Four Hundred And Eighty
2	N/A	N/A	Minimum 12 mm thick cement sand (F.M. 1:2) plaster with neat cement finishing to plinth wall with cement (1:4) up to 150 mm below ground level including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	sqm	136.960	400.000	Four Hundred	54784.000	Fifty-Four Thousand Seven Hundred And Eighty-Four
3	N/A	N/A	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	sqm	136.960	200.000	Two Hundred	27392.000	Twenty-Seven Thousand Three Hundred And Ninety-Two
4	N/A	N/A	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in 2 coats over single coat anti-corrosive coating including cleaning, drying, making	sqm	295.962	500.000	Five Hundred	147981.000	One Lakh Forty-Seven Thousand Nine Hundred And Eighty-One

			free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.						
5	N/A	N/A	Supplying, fitting and fixing SS galvanized barbed wire (dia 2.5 mm) fencing in a circular shape of 100 mm pitch fitted with SS rod casing (made by 6 nos. 10 mm dia SS solid bar(304 grade) in a circular pattern and placed at equal interval), 38 x 38 x 6 mm S.S. angle(304 grade) Y-post 600 mm vertical and 450 mm inclined placed @ 1.5 m c/c (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) and including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supply of all necessary materials complete in all respect and accepted by the Engineer-in-charge. 450 mm circular dia	m	24.000	850.000	Eight Hundred And Fifty	20400.000	Twenty Thousand Four Hundred
6	N/A	N/A	Supply and Installation 6 inch M.S Metal spick 50mm c/c on pump house main gate by welding and finishing with 3 coats of anti-corrosive paint etc. all complete as per design, drawing and direction of E-I-C.	rm	9.150	2000.000	Two Thousand	18300.000	Eighteen Thousand Three Hundred
7	N/A	N/A	Fitting, fixing & readjusting pump house main gate & pump house gate etc. all complete as per direction of E-I-C.	nos	9.000	5000.000	Five Thousand	45000.000	Forty-Five Thousand
7	N/A	N/A	Construction of DWASA Logo (Monogram)	nos	12.000	3100.000	Three Thousand One Hundred	37200.000	Thirty-Seven Thousand Two Hundred
9	N/A	N/A	Materials Loading, unloading & Monogram Painting	nos	3.000	6000.000	Six Thousand	18000.000	Eighteen Thousand
							Grand Total:	437537.000	Four Lakh Thirty-Seven Thousand Five Hundred And Thirty-Seven

This Bill of Quantities is Electronically Signed by Mr. Md. Hossain on behalf of R M Construction