

Office Of the Executive Engineer					
Pagla Sewage Treatment Plant Division, Dhaka WASA					
Name of the work: Rewinding, Repair, maintenance & servicing of 02(Two) set 1.5 KW 0.2 cubic meter/min capacity pump motor of Narinda pumping station & Old airport SLS under PSTP.					
Item No.	Description of Goods	Unit	Quantity	Rate	Amount = (5x6)
1	Supply of 19 SWG super enamel copper wire for re-winding.	kg	8.00	1536.000	12288.000
2	Supply of leatheroid paper (heat-resistant).	Meter	2.00	1000.000	2000.000
3	Supply of ampere cloth.	Meter	2.00	250.000	500.000
4	Supply of Ampere Tube 2, 3,4,5,6 size (heat-resistant).	dozen	2.00	200.000	400.000
5	Supply of Cotton Tape 1 Inch X 150 feet (heat-resistant).	dozen	2.00	699.000	1398.000
6	Supply of nitto golden varnish (Japan).	gallon	1.00	3917.000	3917.000
7	Supply of NC thinner (T-6)	liter	5.00	600.000	3000.000
8	The above mentioned pump-motor for repair & maintenance have to be carried away from diferent SLS, Narinda CPS & PSTP Division to contractor's workshop and returned to the same place after completing the works.	trip	2.00	2000.000	4000.000
9	Dismantling the pump-motor set from basement/foundation.	Each	2.00	1480.000	2960.000
10	Removal burnt wire from motor slot with carefully by local workshop and engaged skilled & experienced electro-mechanical foreman, electrician, mechanics, workers and necessary equipment's, & tools.	Each	2.00	3000.000	6000.000
11	Motor rewinding the supplied materials by local workshop and engaged skilled & experienced mampower and fitting-fixing. Two coad head varnish, cable connection with 100% leakproof works all completed.	Each	2.00	4600.000	9200.000
12	Installation & testing of repaired pump motor sets by engaged skilled foreman, mechanics, electrician, helper with necessary tools & equipments in presence of engineer-in-charge.	Job	1.00	4000.001	4000.001
				Grand Total Tk.	49663.001
				Say,	49663.000
Taka(in words): Forty Nine Thousand Six Hundred Sixty Three Only					

৫/১১/২৫
সম্রাট মিহা
উপ-সহকারী প্রকৌশলী
পাগলা পয়ঃ শোধনাগার বিভাগ
ঢাকা ওয়াসা।

৫/১১/২৫
মোঃ সাইফুল ইসলাম
উপ-বিভাগীয় প্রকৌশলী
পাগলা পয়ঃ শোধনাগার বিভাগ
ঢাকা ওয়াসা

S. Saharun
সৈয়দ শিহাবুর রহমান
নির্বাহী প্রকৌশলী
পাগলা পয়ঃ শোধনাগার বিভাগ
ঢাকা ওয়াসা।