

Office of the Executive Engineer

Savar-Keraniganj Wellfield Plant


Dhaka WASA.


Subject: Removing sludge or semi-liquid clay/substances from backwash common drain of sand filter on IRP#1 under SKWP .

BOQ

Sl. No.	Description of items	Unit	Rate Basis	Quantity	Rate	Amount TK
1	Removing sludge or semi-liquid clay/substances etc not suitable for pumping out or carrying by head load from the bottom of any marshy land, lake, ditch, pond by mixing fine local sand of minimum F.M. 0.8 to a proportion such that it can be carried to an intermediate point of disposal and cutting the same including stacking and spreading properly on a suitable place to dry in the sun for a certain days and dispose the dried sludge or clay to a safe distance etc. complete and accepted by Engineer-in-charge subject to submit method statement to the engineer in charge for carrying out the works including ultimate disposal of the sludge under this item for approval. However, engineer's approval shall not relieve the Contractor of his responsibilities and obligations under the contract.	Cum	PWD rate-2022, Item-2.9	47.048	1054.000	49588.065
Total=						49588.065
Say Total=						49588.000
In words: Forty nine thousand Five hundred and Eighty-eighty only.						



18.12.2023
মোঃ রেজাউল করিম
উপ-সহকারী প্রকৌশলী
সভার-কোরানিগঞ্জ ওয়েলফিল্ড প্রক্ট, ঢাকা ওয়াসা।


৩৬/১২/২৩
জাফর ইকবাল চৌধুরী
সহকারী প্রকৌশলী
সভার-কোরানিগঞ্জ ওয়েলফিল্ড প্রক্ট, ঢাকা ওয়াসা।


১৮/১২/২৩
মাসুদুল আলম
নিবাহী প্রকৌশলী
সভার-কোরানিগঞ্জ ওয়েলফিল্ড প্রক্ট, ঢাকা ওয়াসা।

Office of the Executive Engineer							
Savar-Keraniganj Wellfield Plant							
Dhaka WASA.							
Subject: Removing sludge or semi-liquid clay/substances from backwash common drain of sand filter on IRP#1 under SKWP .							
Calculation Sheet							
Sl. No.	Description of items	Unit	Length	Width	Height	No.	Quantity
1	A. Sand filter (IJKL)	Cum	12.000	0.850	1.500	1.000	15.300
	B. Sand filter (EFGH)	Cum	12.000	0.850	1.300	1.000	13.260
	C. Sand filter (ABCD)	Cum	15.000	0.850	1.450	1.000	18.488
Total=							47.048


 18.12.2023
 মোঃ রেজাউল করিম
 উপ-সহকারী প্রকৌশলী
 (সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।)


 জাফর ইকবাল চৌধুরী
 সহকারী প্রকৌশলী
 (সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।)


 নিবিশি প্রকৌশলী
 (সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।)