

M/S. MAHI & CO

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	DWASA D-64 1.13	Demolisation of the existing RCC/CC/Brick sewer deckslab/foundation/ wall/railing /abutment/ beam etc.with soling under RCC/CC in bed wiyhout disturbing the foundation soil and dumping the materials to a safe place as per direction of the Engineer.	cum	30.000	1251.001	One Thousand Two Hundred and Fifty-One point Zero Zero One	37530.030	Thirty-Seven Thousand Five Hundred and Thirty point Zero Three	I have seen
2	Civil	App. Rate	Earth work in excavation up to the required depth for pipeline chamber all kinds of soil precautions necessary to avoid damage of under ground utility services including removing the excavated earth & stacking the same to safe distance. de-watering machine will be install for maintain the excavation site to dry condition at all time and disposal of surplus excavated materials etc by daily labour. all complete as per direction of the Engineer.	person	80.000	647.001	Six Hundred and Forty-Seven point Zero Zero One	51760.080	Fifty-One Thousand Seven Hundred and Sixty point Zero Eight	I have seen
3	Civil	DWASA D-86 8.1.b	Removal of Excavated Earth and clean the site for a smooth traffic movement during execution of the works and as per direction of the Engineer-in charge.	cum	65.000	288.001	Two Hundred and Eighty-Eight point Zero Zero One	18720.065	Eighteen Thousand Seven Hundred and Twenty point Zero Six Five	I have seen
4	Civil	DWASA 53 5/1	Extra-over item 1 for the provision of Temporary shoring and boxing to the sides of the excavation to maintain a safe working environment upto a depth of 8 m.. The rate to include for the supply of all materials of approved quality; preparation and fixing of the sheeting and removal after the completion of construction; all in accordance with the Technical Specification. Planks and runners shall be minimum 50 mm & 75mm thick and struts shall be minimum 100 mm diameter. (After completion of the work the materials will be the property of contractor)Garjan wooden planks runner block (withdrawn after completion of work).	cum	12.000	3624.001	Three Thousand Six Hundred and Twenty-Four point Zero Zero One	43488.012	Forty-Three Thousand Four Hundred and Eighty-Eight point Zero One Two	I have seen
5	Civil	DWASA 54 9/1	Extra-over item 1 for the provision of Temporary shoring and boxing to the sides of the excavation to maintain a safe working environment upto a depth of 8 m.. The rate to include for the supply of	m	150.000	60.001	Sixty point Zero Zero One	9000.150	Nine Thousand point One Five	I have seen

			all materials of approved quality; preparation and fixing of the sheeting and removal after the completion of construction; all in accordance with the Technical Specification. Planks and runners shall be minimum 50 mm & 75mm thick and struts shall be minimum 100 mm diameter. (After completion of the work the materials will be the property of contractor)Salbullah strut(100mm average dia)							
6	Civil	DWASA 53 5/1	a)Extra over item I for supply and placing of saturated river sand back filling at all required depth in accordance with the technical specification and the standard detail drawing for all water pipe line diametersBending and surrounding by River Saturated Sand (F.M 0.8)	cum	65.000	503.001	Five Hundred and Three point Zero Zero One	32695.065	Thirty-Two Thousand Six Hundred and Ninety-Five point Zero Six Five	I have seen
7	Civil	PWD-18 3.1	One layer of brick flat soling in foundation or in floor with first class or picked jhama bricks including preparation of bed and filling the interstices with local sand leveling etc.	sqm	45.000	420.001	Four Hundred and Twenty point Zero Zero One	18900.045	Eighteen Thousand Nine Hundred point Zero Four Five	I have seen
8	Civil	PWD-18 3.4.1	Mass concrete (1:3:6) in foundation or floor with cement sand (F.M. 1.2) and picked jhama chips including breaking chips screening mixing laying compacting to levels and curing for at least 7 days including the supply of water electricity and other charges and costs of tools and plants etc. all complete and accepted by the Engineer.(Cement: CEM-II/A-M)	cum	12.000	6647.001	Six Thousand Six Hundred and Forty-Seven point Zero Zero One	79764.012	Seventy-Nine Thousand Seven Hundred and Sixty-Four point Zero One Two	I have seen
9	Civil	DWASA D-87 8.11	Hire Charge of de-watering pump. Bailing out of all from pipe line trench with supply of De- watering pump required size including supplying of fuel lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc. all complete as per direction of the E/C.	day	10.000	1861.952	One Thousand Eight Hundred and Sixty-One point Nine Five Two	18619.520	Eighteen Thousand Six Hundred and Nineteen point Five Two	I have seen
10	Civil	M/R	Hire Charge of Generator for Electro fusion machine de-watering and lighting work.	day	10.000	2000.001	Two Thousand point Zero Zero One	20000.010	Twenty Thousand point Zero One	I have seen
11	Civil	DWASA D-68 8.11	Mobilization Demobilization and cleaning go the work site removal of debris and other materials from inside the site restoration of the finished ground surface filling the surrounding ground surface removing contractors materials shades machinery etc from the work site after completion of the works up to satisfaction of the Engineer-in-charge.	Item	3.000	12950.001	Twelve Thousand Nine Hundred and Fifty point Zero Zero One	38850.003	Thirty-Eight Thousand Eight Hundred and Fifty point Zero Zero Three	I have seen
12	Civil	M/R	Safety Barricade & Lighting flag etc.	L.S.	1.000	10000.007	Ten Thousand point Zero Zero Seven	10000.007	Ten Thousand point Zero Zero Seven	I have seen
							Grand Total:	379326.999	Three Lakh Seventy-Nine Thousand	

									Three Hundred and Twenty-Six point Nine Nine Nine	
--	--	--	--	--	--	--	--	--	--	--

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Khan on behalf of M/S. MAHI & CO