

Payment In-Voice

Name of the Work: Repairing of leakage and Removal of polluted water at West Shewrapara, Shewrapara Ananda bazar, South-West Shewrapara and its surrounding area under MODS Zone-4, Dhaka WASA.

SL No	Description of the item	Unit	Quantity	Rate (Tk.)	Amount (Tk.)
1	Pvc pipe laying & fitting work				
	(b) 150 mm dia "C" class pvc pipe	P/M	32	805.001	25760.032
2	(c) 200 mm dia "C" class pvc pipe	P/M	16	1216.001	19456.016
3	(e) 300 mm dia "C" class pvc pipe	P/M	12	2678.001	32136.012
4	150×150×150mm dia pvc Tee	P/M	6	1028.001	6168.006
5	200×150×200mm dia pvc Tee	P/M	8	1489.001	11912.008
6	PVC bend 90° 'C' class 150mm Dia	P/Nr	6	1130.001	6780.006
7	PVC bend 90° 'C' class 200mm Dia	P/Nr	8	2004.001	16032.008
8	PVC End Cap 150mm "C" Class	P/Nr	20	512.001	10240.020
9	PVC End Cap 200mm "C" Class	P/Nr	13	847.001	11011.013
10	a) 200 mm dia service clamp	Pair	20	550.001	11000.020
11	b) 150 mm dia service clamp	Pair	14	450.001	6300.014
12	a) 150 mm dia C.I D/C coupling	P/Nr	18	1227.001	22086.018
13	b) 200 mm dia C.I D/C coupling	P/Nr	16	1450.001	23200.016
14	c) 300 mm dia C.I D/C coupling	P/Nr	8	2625.001	21000.008
15	Palisading work	sqm	72.96	613.001	44724.553
16	Bedding and surrounding by river saturated Sand. (60*0.6*0.76)-((3.14*.20)/4)*60 +((1.52*1.52*.60)*15)=46.27m3	cum	46.27	1088.001	50341.806
17	Backfilling 60*0.76*0.91+(15*(1.52*1.52*0.91))=73.03 m3	cum	73.03	207.001	15117.283
18	Excavation (60*0.76*1.52)+(15*(1.52*1.52*1.52))=121.99 m3	cum	121.99	288.001	35133.242
19	DN 20 to DN 25 mm dia	P/Nr	14.00	1216.001	17024.014
20	DN 32 to DN 50 mm dia	P/Nr	10.00	2021.001	20210.010
21	Placing of Mass concrete (1:3:6)0.4m3*5=2.0 m3	cum	2	8886.001	17772.002
22	Hire charge of de-watering Pump	P/day	17	1862.001	31654.017
23	Providing compacted sub-base course (50x0.76x0.15)=5.7 m3	cum	5.7	5449.001	31059.306
24	Road Safety measures and tools as per direction of Engineer in Charge.	LS	1	4000.001	4000.001

Grand Total = 490117.431

As per 5% less Amount Of TK = 24505.872

Grand Total Amount of TK= 465611.559

In Word: Four Lakh Sixty Five Thousand Six Hundred Eleven Point Five Five Nine Taka only.

30/3/24

মোঃ মাইদুল ইসলাম
: উদ-সহকারী প্রকৌশলী
মডুস জোন-৪, ঢাকা ওয়াসা।

30/03/24

মোহাম্মদ বিদ্রাল হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৪, ঢাকা ওয়াসা

30.03.2024

Md. Mazharul Islam
Executive Engineer
MODS Zone-4, Dhaka, WASA