


Payment In-voice

Name of work : Repair & Maintenance of pump house, Chlorine room, Boundary wall and necessary renovation works of South Pallabi and Pallabi Overhead water pump compound under MODS Zone-4, Dhaka WASA.

SL		Site Development	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		BOQ rate	Total TK
1	Site Development	South Pallabi Water Pump	32	24	1		768	cft	21.77		481.001	18922.579
		Pallabi Overhead Water Pump	31	20	1		620		17.57			
		Total							39.34	cum		
2	Patent Stone	Patent Stone	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		566.001	15780.108
		South Pallabi Water Pump	14	12	0		168	sft				
		Pallabi Overhead Water Pump	12	11	0		132					
		Total						300	sft	27.88	sqm	
3	South Pallabi Water Pump	Stripping of Plaster	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		31.001	9807.476
		Boundary Wall	118.00	0.00	3.00	2	708.00					
		Pump House	40.00	0.00	10.00	2	800.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
	Pallabi Overhead Water Pump	Boundary Wall	100.00	0.00	3.00	2	600.00					
		Pump House	41.00	0.00	10.00	2	820.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
		Sub Total						3404.00	sft	316.36	sqm	
4	South Pallabi Water Pump	Plaster Work	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		316	99969.760
		Boundary Wall	118.00	0.00	3.00	2	708.00					
		Pump House	40.00	0.00	10.00	2	800.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
	Pallabi Overhead Water Pump	Boundary Wall	100.00	0.00	3.00	2	600.00					
		Pump House	41.00	0.00	10.00	2	820.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
		Sub Total						3404.00	sft	316.36	sqm	
5		Brick Work	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		7529.001	14907.422
		South Pallabi Water Pump	35.00	0.41	2.00	1	28.70					
		Pallabi Overhead Water Pump	40.00	0.41	2.50	1	41.00					
		Sub Total						69.70	cft	1.98	cum	
6	South Pallabi Water Pump	Exterior Emulsion Paint	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		177.001	58348.380
		Boundary Wall	118.00	0.00	5.00	2	1180.00					
		Pump House	40.00	0.00	11.00	1	440.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
	Pallabi Overhead Water Pump	Boundary Wall	100.00	0.00	5.00	2	1000.00					
		Pump House	41.00	0.00	11.00	1	451.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
		Sub Total						3547.00	sft	329.65	sqm	
7	South Pallabi Water Pump	Interior Emulsion Paint	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		155.001	22847.147
		Pump House	40.00	0.00	10.00	1	400.00					
		Ceiling	14.00	12.00	0.00	1	168.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
	Pallabi Overhead Water Pump	Pump House	41.00	0.00	10.00	1	410.00					
		Ceiling	12.00	11.00	0.00	1	132.00					
		Chlorine Room	17.00	0.00	7.00	1	119.00					
		Toilet	17.00	0.00	7.00	1	119.00					
		Sub Total						1586.00	sft	147.40	sqm	




		Site Development	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.		BOQ rate	Total TK
8	South Pallabi Water Pump	Enamel Paint	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.			
		Door	7.00	3.00		2	42.00					
		Window	4.00	3.00		2	24.00					
		Grill Fencing	118.00		3.00		354.00					
		Gate	14.00	7.00		1	98.00					
	Pallabi Overhead Water Pump	Door	7.00	4.00		2	56.00					
		Window	7.00	4.00		2	56.00					
		Gate	14.00	7.00		1	98.00					
		Grill Fencing	100.00		3.00		300.00					
		Sub Total						1028.00	sft	95.54	sqm	183.001
9		Grill Fencing	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.			
	South Pallabi Water Pump	Boundary Wall	36.00		3.00	1	108.00					
	Pallabi Overhead Water Pump	Boundary Wall	40.00		3.00	1	120.00					
	Sub Total						228.00	sft	21.19	sqm	5254.001	111332.281
10		MS Gate	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.			
	South Pallabi Water Pump		12.00		7.00	1	84.00					
	Pallabi Overhead Water Pump		12.00		7.00	1	84.00					
	Sub Total						168.00	sft	15.61	sqm	6667.001	104071.886
11		Site Cleaning	Length (ft.)	Breadth (ft.)	Height (ft.)	Number/Side	F.P.S		M.K.S.			
	South Pallabi Water Pump		27.00	15.00	1.00	1	405.00					
	Pallabi Overhead Water Pump		21.00	15.00	1.00	1	315.00					
	Sub Total						720.00	cft	20.41	cum	808.001	16491.300
Total =												489962.255

In Word : Four Lakh Sixty Five Thousand Four Hundred Sixty Four Point One Four Two Taka Only.

26/03/28
 ব্রিয়া আনাদিন চৌধুরী
 উপ-সহকারী প্রকৌশলী
 মডুস জোন-৪
 ঢাকা ওয়াসা

28/03/24
 মোঃ কায়কোবাদ হোসেন
 সহকারী প্রকৌশলী
 মডুস জোন-৪, ঢাকা ওয়াসা

28.03.24
 Md. Mazharul Islam
 Executive Engineer
 MODS Zone-4, Dhaka, WASA