


[View All Notifications](#)

Priced Bill of Quantities (BOQ)

[Tender/Proposal Document](#)

Tender/Proposal Detail

Tender/Proposal ID :	925148	Invitation Reference No. :	46.05.0000.412.92.026.2023-24/eT-32
Closing Date and Time :	02-Jan-2024 13:00	Opening Date and Time :	02-Jan-2024 13:00
Procuring Entity :	Office of the EE, MODS Zone-7, Dhaka WASA		
Brief :	Repairing and maintenance of pump house, grill and gate and sand filling at Nayanagar and Mridhabari works under MODS Zone-7 area, Dhaka WASA.		
Tender/Proposal Status :	Contract Awarded		

[View Notice](#)

Lot Detail

Lot No. :	B 14.7
Lot Description :	Repairing and maintenance of pump house, grill and gate and sand filling at Nayanagar and Mridhabari works under MODS Zone-7 area, Dhaka WASA.

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	-	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the Engineer.	Cum	80.884	635.001	Six Hund	51361.42	Fifty-One	- v
2	Civil	-	One layer of brick flat soling in foundation or in floor with first class or picked jhama bricks including preparation of bed and filling the interstices with local sand, leveling etc. complete and accepted by the Engineer.	Sqm	26.002	420.001	Four Hund	10920.86	Ten Thous	- v
3	Civil	-	Mass concrete in foundation (1:3:6) with cement, brick chips and sand of F.M. 1.2panels, compacting and finishing the top with neat cement and curing at least 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer.(Cement: CEM-II/A-M) In ground floor	Cum	1.643	6647.001	Six Thou	10921.02	Ten Thous	- v
4	Civil	-	Supplying, fitting and fixing window grills made of 16 mm dia M.S. rod @ 100 mm c/c fitted with 3 (three) nos. horizontal M.S. flat bar (38 mm x 6 mm) including fabrication, welding, riveting, cost of electricity, workshop charges, carriage, fixing with pre-placed clamps in wall/RCC member for all floors etc. complete and accepted by the Engineer-in-charge. (Total weight per sqm should be approx. 22.8 kg and add or deduct @ Tk. 97.00 for each kg/sqm excess or less respectively)	Sqm	13.011	2206.001	Two Thou	28702.27	Twent y-Eight	- v
5	Civil	-	Supplying, fitting, fixing, and installation of ordinary type M.S. security gate of any design and shape with 50 mm x 50 mm x 6 mm M.S. angle outer frame and 02 (two) 50 mm x 50 mm x 6 mm angle placed diagonally having 22 mm dia M.S. rod placed vertically @ 115 mm c/c. and also 38 mm x 6 mm F.I placed horizontally, the bottom part covered with 3 mm thick M.S. sheet providing locking arrangements on 3 mm thick M.S. plate providing heavy type clamps fitted and fixed with the outer frame of the main gate, the clamp being embedded in R.C.C. or R.C. core pillar with cement concrete (1:2:4) in masonry including cutting holes and mending good the damages, finishing, curing etc. including fabrication, riveting, welding as and where necessary, etc. all complete as per drawing, design and accepted by the Engineer-in-charge.	Sqm	15.610	5289.001	Five Thou	82561.30	Eighty-Two	- v
6	Civil	-	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to wall both inner-and outer surface, finishing the corner and edges including washing of sand cleaning the surface, scaffolding and curing at least for 7 days, cost of water, electricity and other charges etc. all complete in all respect as per drawing and accepted by the Engineer. (Cement: CEM-II/A-M). Ground floor.	Sqm	254.647	243.001	Two Hund	61879.47	Sixty-One	- v

7	Civil	-	Painting to door and window frames and shutters in two coats with approved best quality and colour of standard synthetic enamel paint delivered from authorized local agent of the manufacturer in a sealed container, having highly water resistant, high bondability, flexible, using specific brand thinner applied by brass/roller/spray over a coat of priming elapsing time for drying including surface cleaning from dust, oil or dirt, smoothening, finishing and polishing with sand paper and necessary tools, scaffolding, testing charges etc. all complete in all floors approved and accepted by the Engineer.	Sqm	110.857	189.001	One Hund ▴ ▾	20952.08	Twenty ▴ ▾	- ▾
8	Civil	-	Supplying, fitting and fixing Special/Fancy quality C.P. concealed/ Surface Angle stop cock etc. complete approved and accepted by the Engineer.	Each	2	853.001	Eight Hund ▴ ▾	1706.002	One Thous ▴ ▾	- ▾
9	Civil	-	Providing and fixing of 20 watt Energy Saving light(LED) Fitting of consisting of superior quality holder, 18 SWG Sheet stove evameled base vecessary wiring etc.complete (except lamp) of following model and as per sample approved by the Engineer-in-charge.	Nos	12	320.001	Three Hund ▴ ▾	3840.012	Three Thous ▴ ▾	- ▾
10	Civil	-	Concealed conduit wiring for following point looping at the switch board with earth terminal including circuit wiring with IC-2x1.5 sq. mm PVC insulated and sheathed stranded cable (BYM) & 1.5 sq. mm PVC insulated green/white coloured ECC wire (BYA) through PVC conduit (Lira brand or equivalent product of other reputed manufacturer) of min. 25 mm dia & 1.5 mm wall thickness complete with 18 SWG GP sheet, switch board and pull box with 3mm thick ebonite sheet cover, 5 amps piano switch, ceiling rose, fixing materials etc. as required including mending the damages good (all electrical contacts shall be of brass/copper). With Cables manufactured by M/S Eastern Cables Ltd. a) Light point	Nos	10	1443.001	One Thou ▴ ▾	14430.01	Fourteen ▴ ▾	- ▾
11	Civil	-	b) Fan point	Nos	2	1570.001	One Thou ▴ ▾	3140.002	Three Thous ▴ ▾	- ▾
12	Civil	-	Supply and fixing of A/C capacitor type ceiling fan of following sizes complete with 3048mm (12") long down rod blades, canopy, regulator, conncting PVC wire complete as required,a)1422.4mm (56?) sweep (Delux, Jamuna brand)	Nos	2	3399.001	Three Thou ▴ ▾	6798.002	Six Thous ▴ ▾	- ▾
							Grand Total :	297212.4		