

Office of the Executive Engineer							
MODS Zone-8, Dhaka WASA							
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.							
Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front of Kuril Hazibari Mosjid at DMA-802 under MODS Zone-8, Dhaka WASA							
Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	75 mm dia HDPE Pipe	8.00	P/M	485.001	3,880.008	
2	Approved Rate	75 mm dia HDPE Sleeve E.F	2	Nos			Supply by Sub store
3	Approved Rate	Excavation and removal of soil from the trench up to the required depth in accordance with the technical specification and direction of Engineering in charge, (9*1*2)= 18 cum	18.000	Cum	331.000	5958.000	
4	Approved Rate	Supplying, depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge. (9*1*2)= 18 cum	18.000	Cum	578.000	10404.000	
5	Approved Rate	Dismantling of the existing CC Road with brick flat soling under CC bed and dumping the materials to a safe place as per direction of the Engineer. (9*1*0.3)=2.7 cum	2.700	p/m³	1250.001	3375.003	
	PWD soR 2022 (Revised) (03.1.1)	One layer brick flat soling in foundation with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling etc. complete and accepted by the Engineer-in-charge. (9*1)= 9 sqm	9.000	p/sqm	636.001	5724.009	
	PWD soR 2022 (Revised) (03.4.1)	Placing lean/ blinding concrete (1:3:6) in foundation r with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days in accordance with Technical Specification and direction of Engineering in charge. (9*1*1.15)=1.35 Cum	1.350	p/m³	9,362.001	12638.701	
	Approved Rate	Hiring Charge of De-Watering Pump	2.000	day	2,141.001	4282.002	
6	Approved Rate	Mechanics Charge	2.000	P/Person	1000.000	2000.000	
Total=						48261.723	

In words: Forty Eight Thousand Two Hundred Sixty One Point Seven Two Three Taka Only.

18/03/24
ইমামুল ইসলাম
উপ-সহকারী প্রকৌশলী
মডুস জোন-০৮, ঢাকা ওয়াসা।

19.03.24
মোঃ মানিক হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৮, ঢাকা ওয়াসা।

১৯/০৩/২৪
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডুস জোন-৮
ঢাকা ওয়াসা।