


[View All Notifications](#)

Priced Bill of Quantities (BOQ)

[Tender/Proposal Document](#)

Tender/Proposal Detail

Tender/Proposal ID :	868932	Invitation Reference No. :	46.05.0000.424.37.119.23.37
Closing Date and Time :	25-Sep-2023 14:00	Opening Date and Time :	25-Sep-2023 14:00
Procuring Entity :	Office of the EE, Field Maintenance Division-2, Dhaka WASA		
Brief :	Repairing-maintenance & re-construction of Tin shed store room floor with related works at F.M.D-2, DWASA.		
Tender/Proposal Status :	Contract Awarded		

[View Notice](#)

Lot Detail

Lot No. :	46.05.0000.424.37.119.23.37
Lot Description :	Repairing-maintenance & re-construction of Tin shed store room floor with related works at F.M.D-2, DWASA.

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	A	NA	Stripping of unserviceable plaster including racking out joints, cleaning etc. =84'x31'=2604²ft=242.04 m2	sqm	242.04	31.001	Thirty -One	7503.482	Seven Thous	- v
2	A	NA	Picking-up of unserviceable patent stone from floor and dado etc. and removal of debris to a safe distance. =84'x31'=2604²ft=242.04 m2	sqm	242.04	47.001	Forty-Seve	11376.12	Eleven Thous	- v
3	A	NA	38 mm thick artificial patent stone (1:1.5:3) flooring with cement, best quality coarse sand (50% quantity of Sylhet sand or coarse sand of equivalent F.M. 2.2 and 50% best quality local sand of FM 1.2) and 12 mm down well graded stone chips, laying the concrete in alternate panels, compacting and finishing the top with neat cement and curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge.(Cement: CEM-II/B-M) In ground floor. all complete as per accepted by the Engineer-in-charge. Total area= =84'x31'=2604²ft=242.04 m2	sqm	242.04	741.001	Seve n	179351.8	One Lakh	- v
4	A	NA	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to plinth wall with cement (1:4) up to 150 mm below ground level including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.Total area= =84'x31'=2604²ft=242.04 m2	sqm	242.04	362.001	Three Hund	87618.72	Eighty-Seven	- v
5	A	NA	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	sqm.	289.63	299.001	Two Hund	86599.66	Eighty-Six	- v
6	A	NA	White washing by three coats, lime mixture prepared at least 12 hours before use, slacking stone lime, supply of gums, blue, stirring thoroughly, removing the floating materials from the mixer, surface cleaning to free from all foreign materials before application of each coat, applying one vertical and one horizontal wash for each coat and successive coat is to be applied after drying up of previous coat including hair brass, providing necessary scaffolding and cleaning plinth, floors, doors, windows, portions and ventilators by washing, rubbing, oiling if necessary after white wash for all floors including cost of water, electricity and other charges etc. complete in all respect in all floors and accepted by the Engineer.	sqm.	289.63	25.002	Twent y-	7241.329	Seven Thous	- v
7	A	NA	Colour wash with yellow orchard/any other colour pigment by two coats over a prime coat of white wash, lime mixture prepared at least 12 hours before use, slacking stone lime, supply of gums, blue, stirring thoroughly,	sqm.	289.63	28.001	Twent y-	8109.930	Eight Thous	- v

			removing the floating materials from the mixer, surface cleaning to free from all foreign materials before application of each coat, applying one vertical and one horizontal wash for each coat and successive coat is to be applied after drying up of previous coat including hair brass, providing necessary scaffolding and cleaning plinth, floors, doors, windows, portions and ventilators by washing, rubbing, oiling if necessary after white wash for all floors including cost of water, electricity and other charges etc. complete in all respect in all floors and accepted by the Engineer.							
8	A	NA	Standard emulsion plastic paint of approved best quality and color delivered from authorized local agent of the manufacturer in a sealed container having high water resistance, high bondability, flexibility property using specified brand thinner applying interior wall and ceiling with surface preparation including cleaning, drying, making free from dirt, grease, wax, etc. all complete as per direction of the engineer in charge.	sqm	289.63	258.001	Two Hund	74724.830	Seventy-Four	-
9	A	NA	Painting to door, collapsible gate and rack frames and shutters in two coats with approved best quality and colour of Premium synthetic enamel paint delivered from authorized local agent of the manufacturer in a sealed container, having highly water resistant, high bondability, flexible, using specific brand thinner applied by brass/roller/spray over a coat of priming elapsing time for drying including surface cleaning from dust, oil or dirt, smoothening, finishing and polishing with sand paper and necessary tools, scaffolding, testing charges etc. all complete in all floors approved and accepted by the Engineer.	sqm.	106	238.001	Two Hund	25228.100	Twenty-Five	-
10	A	NA	Loading unloading all materials at Tin shed store to another store and after finishing floor works, then return this materials at same place.	item	1	9999.999	Nine Thou	9999.999	Nine Thous	-
							Grand Total :	497754.000		

[Home](#) | [About e-GP](#) | [Contact Us](#) | [RSS Feed](#) | [Terms and Conditions](#) | [Service Level](#) | [Disclaimer and Privacy Policy](#) | [New Features](#)

Best viewed in 1024 x 768 and above resolution. Browsers Tested & Certified by CPTU: Internet Explorer 8.x, 9.x, 10.x, 11.x and Mozilla Firefox 13.x, 14.x, 29.x, 52.x, 53.x, 62.x, 70.x, 71.x, 72.x, 77.x and Google Chrome 79.x

Copyright © 2011 Central Procurement Technical Unit (CPTU). All Rights Reserved.

IMED, Ministry of Planning, Government of the People's Republic of Bangladesh