

M/S. SUNAM ENTERPRISE**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	N/A	Stripping of unserviceable plaster	Sqm	319.200	31.001	Thirty-One point Zero Zero One	9895.519	Nine Thousand Eight Hundred and Ninety-Five point Five One Nine	I have seen
2	Civil	N/A	Taking out old/tear barbed wire	m	76.000	9.001	Nine point Zero Zero One	684.076	Six Hundred and Eighty-Four point Zero Seven Six	I have seen
3	Civil	N/A	125 mm brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) In ground floor	Sqm	45.600	1185.001	One Thousand One Hundred and Eighty-Five point Zero Zero One	54036.046	Fifty-Four Thousand AND Thirty-Six point Zero Four Six	I have seen
4	Civil	N/A	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:6) having with fresh cement to both inner and outer surface of wall, finishing the edges and corners including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	Sqm	319.200	291.001	Two Hundred and Ninety-One point Zero Zero One	92887.519	Ninety-Two Thousand Eight Hundred and Eighty-Seven point Five One Nine	I have seen

5	Civil	N/A	Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer (Berger weather coat smooth/Elite smooth exterior/ Asian apex weather coat or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-incharge.	Sqm	740.240	298.001	Two Hundred and Ninety-Eight point Zero Zero One	220592.260	Two Lakh Twenty Thousand Five Hundred and Ninety-Two point Two Six	I have seen
6	Civil	N/A	Supplying, fitting and fixing 12 BWG barbed wire (2 ply, 4 points) in fencing work @ 150 mm c/c both horizontally and vertically, supported by 38 mm x 38 mm x 6 mm M.S. Y-shape angle post (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) 600 mm vertical and 450 mm inclined or as per requirement @ 2.4 m c/c including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supplying all necessary materials complete in all respect and accepted by the Engineer-incharge. (Rate is excluding the cost of R.C.C or brick work or C.C. which is to be paid as per corresponding items in the schedule)	m	50.000	1034.001	One Thousand AND Thirty-Four point Zero Zero One	51700.050	Fifty-One Thousand Seven Hundred point Zero Five	I have seen
7	Civil	N/A	Making Dhaka WASA Monogram (Height of the monogram =0.75m, width =0.50m) out side of boundary wall (alternatively English & Bangali) and painting to Monogram as per Specification & direction of the Engineering in Charge.	Nos	12.000	5200.001	Five Thousand Two Hundred point Zero Zero One	62400.012	Sixty-Two Thousand Four Hundred point Zero One Two	I have seen

	Civil	N/A	Site Cleaning as per direction of the Engineer in charge.	L.S	1.000	7504.518	Seven Thousand Five Hundred and Four point Five One Eight	7504.518	Seven Thousand Five Hundred and Four point Five One Eight	I have seen
							Grand Total:	499700.000	Four Lakh Ninety-Nine Thousand Seven Hundred	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Hossen on behalf of M/S. SUNAM ENTERPRISE

M/S. SUNAM ENTERPRISE**Tenderer's Quoted Price****Tenderer's Quoted Price**

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
499700.000	-5.000	474715.000	Four Lakh Seventy-Four Thousand Seven Hundred and Fifteen
	Grand Total:	474715.000	Four Lakh Seventy-Four Thousand Seven Hundred and Fifteen

This Tenderer's Quoted Price is Electronically Signed by Mr. Md. Hossen on behalf of M/S. SUNAM ENTERPRISE