

Dipro Construction

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item no.	Group	Item Code (if any)	Description of Item	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	Select 'YES' to see the Grand Total
1	N/A	N/A	Supply of Sodium Hypo Chloride (5.25%) solution 08(Eight) No?s Filter? s (100 Liter per filter) with cleaning work done following by proper Rule as per direction of Engineer-in-charge.	Litter	400.000	175.001	One Hundred And Seventy-Five Point Zero Zero One	70000.400	Seventy Thousand Point Four	Yes
2	N/A	N/A	Supply of wire Brush.	Nos	40.000	150.001	One Hundred And Fifty Point Zero Zero One	6000.040	Six Thousand Point Zero Four	Yes
3	N/A	N/A	Supply of cotton Gloves.	Pair	40.000	50.001	Fifty Point Zero Zero One	2000.040	Two Thousand Point Zero Four	Yes
4	N/A	N/A	"Filter bed sand lifting work: 2 (two) filter beds (No. 5 and No. 6) sand buckets and hoppers should be lifted and placed in open space at a distance of 400 feet. Necessary ropes, buckets, bamboos, ladders shall be used for the work and the work shall be as per the instructions of the engineer in charge. 2x(14.76ft x 28.21ft x 2ft) = 1665.52 cft or 1666.00cft"	Cft	1666.000	42.001	Forty-Two Point Zero Zero One	69973.666	Sixty-Nine Thousand Nine Hundred And Seventy-Three Point Six Six Six	Yes
5	N/A	N/A	"Supply of Sand for 2 (two) filter beds (No. 5 and No. 6) : Sand shall be supplied as per the following specifications and samples (1) Effective size: 0.55-0.65	Cft	499.800	296.001	Two Hundred And Ninety-Six Point Zero Zero One	147941.299	One Lakh Forty-Seven Thousand Nine Hundred And Forty-One Point	Yes

			(2) Uniformity of Coefficient: not more than 1.7 Quantity of Sand(5&6) $2 \times (14.76 \text{ ft} \times 28.21 \text{ ft} \times 2 \text{ ft}) = 1665.52 \text{ cft}$ or $1666.00 \text{ cft} \times 30\% = 499.80 \text{ cft}$						Two Nine Nine	
6	N/A	N/A	" Sand replacement work: Under the base plate of 2 filters (No. 5 and 6) will be replaced by sand lifted and supplied by buckets and shovels through skilled labor. $2 \times (14.76 \text{ ft} \times 28.21 \text{ ft} \times 2 \text{ ft}) = 1665.52 \text{ cft}$ or 1666.00 cft "	Cft	1666.000	37.001	Thirty-Seven Point Zero Zero One	61643.666	Sixty-One Thousand Six Hundred And Forty-Three Point Six Six Six	Yes
7	N/A	N/A	Washing, drying and packaging of withdrawn sand from filter bed. Per sack capacity will be 50 kg.	Job	2.000	17880.001	Seventeen Thousand Eight Hundred And Eighty Point Zero Zero One	35760.002	Thirty-Five Thousand Seven Hundred And Sixty Point Zero Zero Two	Yes
8	N/A	N/A	Supply of Stones: For 2 (two) filters (No. 5 and No. 6) stone shall be supplied according to the sample size. "2 - 5 mm. 5 - 10 mm. 10 - 15 mm. $2' (14.76 \text{ ft} \times 28.21 \text{ ft} \times 1 \text{ ft}) = 832.76 \text{ cft}$ $= 832.76 \times 30\% = 249.828 \text{ cft}$ "	Cft	249.828	316.001	Three Hundred And Sixteen Point Zero Zero One	78945.897	Seventy-Eight Thousand Nine Hundred And Forty-Five Point Eight Nine Seven	Yes
9	N/A	N/A	"Stone replacement work: After running the lifted stone of 2 filters (No. 5 and 6) through the ten-size sieve, the re-lifted and supplied stone shall be placed on top of the bottom layer and arranged in the same way as before. $2' (14.76 \text{ ft} \times 28.21 \text{ ft} \times 1 \text{ ft}) = 832.76 \text{ cft}$ "	Cft	249.828	37.001	Thirty-Seven Point Zero Zero One	9243.885	Nine Thousand Two Hundred And Forty-Three Point Eight Eight Five	Yes
10	N/A	N/A	Supply of High Pressure Flexiblw Hose pipe for cleaning works. Pipe dia: 2 inch; pipe thickness: 2mm.	Meter	55.000	270.001	Two Hundred And Seventy Point Zero Zero One	14850.055	Fourteen Thousand Eight Hundred And Fifty Point Zero Five Five	Yes
							Grand Total:	496358.950	Four Lakh Ninety-Six Thousand Three Hundred And Fifty-	

Dipro Construction

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
496358.952	-5.000	471541.004	Four Lakh Seventy-One Thousand Five Hundred And Forty-One Point Zero Zero Four
	Grand Total:	471541.004	Four Lakh Seventy-One Thousand Five Hundred And Forty-One Point Zero Zero Four

This Tenderer's Quoted Price is Electronically Signed by Mr. Mritunjoy Das on behalf of Dipro Construction