

Office of the Executive Engineer

MODS Zone-9 Dhaka WASA


19, Shahjalal Avenue, Sector #6,

Uttara, Dhaka-1230

Estimate

Name of work: Repairing of leakage at delivery line of Modhubag water pump & Repairing of Modhubag Pump House Floor under MODS Zone-9 Dhaka WASA.


SL no.	Description of the Item	Unit	Quantity	Rate(Tk.)	Amount(Tk.)
1	MS Pipe (Normal) 200 mm dia Thickness	P/M	3	3068	9204.00
2	Extra-Over item 1 for the supply lay of Ductile/Cast iron/M.S/GI fittings for MS pipes in according with the technical specification M.S Bend 45" dia	P/Nr	1	6545	6545.00
3	MS Dresser coupling 200mm dia	P/Nr	2	1600	3200.00
4	Bedding and surrounding by river saturated Sand. 1.5x1.5x3=6.75 m ³	Cum	6.75	1088	7344.00
6	Excavation (1.5x1.5x3) m ³ =6.75 m ³	Cum	6.75	149	1005.75
7	Palisading work by supplying of bitumen drum sheet	sqm	5	520	2600.00
8	Delivery line supporting pillar	L.S	1	5000	5000.00
9	Welding charge	L.S	1	5000	5000.00
10	Hire charge of De-watering Pump	P/Day	2	1862	3724.00
11	cement For Floor	Bag	1	600	600.00
12	Sand For Floor (1.52x1.52x2)=4.62 m ³	Cum	4.62	1088	5026.56
13	Brick For Floor	P/Nos	40	15	600.00
				Total(TK)	49849.31
In Word: Forty Nine Thousand Eight Hundred Forty Nine Point Three OneTaka Only.					


17.09.2023

মোঃ রিফাত আলম
উপ-সহকারী প্রকৌশলী
মডস জোন-৯, ঢাকা ওয়াসা


29/09/2023

মাঃ দেলোয়ার হোসেন
সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা


29/09/23

এস. এম. মাসুদ পারভেজ
সিবিই প্রকৌশলী
মডস জোন-৯, ঢাকা ওয়াসা