

Office of the Executive Engineer

MODS Zone-1

DHAKA WASA


Name of Work: মডস জোন-১ এর আওতাধীন রাস্তার গুরুত্বপূর্ণ স্থাপনা বজায় রাখা কম্পাউন্ডে ওভারহেড ট্যাংক সংলগ্ন পানির লাইনের লিকেজ মেরামত
করান কাজ প্রসঙ্গে।


SL No	Basis of rate	Description of item	Unit	Qty	Rate	Amount
1	2	3	4	5	6	7
1		Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract.	cum	14.4	171.00	2462.40
2	1	Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement Annex --Section --) in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for excavation in all kinds of soil, BFS/HBB/ Bituminous Rd CC RCC rd surface except rock to the full depth of trench required by the specifications, precautions necessary to avoid damage of underground utility services, (any damage Contractor shall repair by his own cost) including removing the excavated earth & stacking the same to safe distance without any traffic obstacles, de-watering of the trench to keep dry condition at all times, including all necessary shoring, boxing, must be protected from any collapse of trench sides, preparation of trench bottom, at depth of 1.2.M, transport (all kinds of materials, equipment, pipes & fittings) to site, laying, jointing and cleaning of the water pipes, disposal of surplus excavated material and transport back surplus materials to Dhaka WASA stores (materials supplied by Dhaka WASA described in Anexure -----) as per specifications and direction of Engineering in charge (cost of excess excavated earth would be deducted as per deptt material rate)				
	1/1.	uPVC Pipe (PN -10) (ISO 4422-2 (1996)				
	d.	160mm dia	P/M	4	1013.00	4052.00
	e.	225mm dia	P/M	4	1938.00	7752.00
3						
4	4	Extra-over item 1 for the supply (including supply of fittings described in schedule of requirement Annex-----) and installation following adopters for jointing components of pipelines, diameter given below, as per specifications and direction of Engineering in charge and the standard detail drawings.				

Spbun

SL No	Basis of rate	Description of item	Unit	Qty	Rate	Amount
	4/4.	MS dresser coupling				
	b.	150mm dia	P/Nr.	2	1468.00	2936.00
5	c.	200mm dia	P/Nr.	2	1840.00	3680.00
6		Skilled Labour	P/No	3	647.00	1941.00
7		Un-Skilled Labour	P/No	6	615.00	3690.00
8	6/b.	A)Extra-over item 1 for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	cum	14.4	578.00	8323.20
9	9	Extra-over item 1 for the excavation and removal of soft soil (on written permission of E/C) from the trench bottom beyond allowable depth and back fill of this by supplying, depositing and compaction in 150 mm layer of fine sand (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge.	cum	14.4	331.00	4766.40
10	16	Shifting and connection of existing Service Lines to improved systems for all depths, diameters, length up to meter chambers at consumers premises. The rate to include all necessary uPVC BS E-class pipes/ PE Pipe , excavation, PVC clamp saddles or CI clamps, quality fittings, valves, appropriate drilling system for making holes in pipes, backfilling with sand (FM 0.8), plugging, de-watering, cleaning, unplugging, fitting fixing of float valve / check valve at the end of service line(in the reservoirs), shifting or change of service meter. The contractor will responsible for work up to the meter chamber and contractor will keep record of service line shifting works. The contractor will arrange to make the meter chamber with cost of consumer if there is no chamber or poor quality chamber. The rate includes all pipes, fittings, materials (domestic meter shall be provided by DWASA), installation arrangement, for necessary diversion and provide water to consumer for disturbing period, pressure test of each connection. After completion of work contractor will				
	16/1	DN 20 to DN 25mm dia	Each	2	1398.00	2796.00
11	20	<u>Hire charge of de-watering Pump.</u>				
		Bailing out of all water from pipe line trench with supply of de-watering pump required size including supplying of fuel lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc. all completed as per direction of the E/C.	P/day	3	2141.00	6423.00
12		Site Cleaning	L/S	2	575.00	1150.00
					Total Taka	49972.00

Taka in word=(Fourty Nine Thousand nine hundred Seventy two) Taka Only.


 02/10/24
 Md. Iqbal Hossain Mollah
 Sub-Assistant Engineer
 MODS Zone-1
 Dhaka WASA


 09/10/24
 Md. Mahedi Hasan
 Assistant Engineer
 MODS Zone-1
 Dhaka WASA


 09/10/24
 Md. Anwar Hossain
 Executive Engineer
 MODS Zone-1
 Dhaka WASA