

M/s Newtral Builders**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	N/A	Earth work in excavation up to the required depth for pipeline chamber all kinds of soil, precautions necessary to avoid damage of under ground utility services, including removing the excavated earth & stacking the same to safe distance. de-watering machine will be install for maintain the excavation site to dry condition at all time and disposal of surplus excavated materials etc. all complete as per Drawing, Specification & Direction of the E/C .For depth to invert exceeding 3.0 m but not exceeding 5.0 m	p/m3	59.460	165.601	One Hundred and Sixty-Five point Six Zero One	9846.635	Nine Thousand Eight Hundred and Forty-Six point Six Three Five	I have seen
2	N/A	N/A	Demonization of the existing RCC/CC/Brick sewer deck slab /foundation /wall/ railing/ aboutment/ beam etc. with soling under RCC/CC in bed, without disturbing the foundation soil and dumping the materials to a safe place as per direction of the Engineer. b) C.C/R.C.C	p/m3	15.770	1438.651	One Thousand Four Hundred and Thirty-Eight point Six Five One	22687.526	Twenty-Two Thousand Six Hundred and Eighty-Seven point Five Two Six	I have seen
3	N/A	N/A	Placing of Reinforced Cement concrete (1:2:4) for the top slab with stone chips 3/4" size and down graded of water pipe line chamber including the supply of all materials, in accordance with Technical Specification and direction of Engineering in charge, and Standard Details Drawings.	p/m3	12.110	6474.501	Six Thousand Four Hundred and Seventy-Four point Five Zero One	78406.207	Seventy-Eight Thousand Four Hundred and Six point Two Zero Seven	I have seen
4	N/A	N/A	Formwork/shuttering, prop and necessary supports etc. (wooden)	p/m2	136.490	292.101	Two Hundred and Ninety-Two point One Zero One	39868.865	Thirty-Nine Thousand Eight Hundred and Sixty-Eight point Eight Six Five	I have seen

5	N/A	N/A	Extra over item 3/1 for the provision of Mild steel reinforcing rods(40grade) all in accordance with the technical specification and standard drawings. The rate to include for supply transportation cleaning of loose rust and bending cutting and fixing with G. I. Binding wire	p/kg	675.000	74.751	Seventy-Four point Seven Five One	50456.925	Fifty Thousand Four Hundred and Fifty-Six point Nine Two Five	I have seen
6	N/A	N/A	Erection of Brickwork (1:4) for the walls 125mm th. Of chamber at any req. depth, all in accordance with Technical Specification and direction of Engineering in charge and standard details drawings. The rate to include for the supply of first class bricks, the preparation of. Sand cement mortar including the supply of all materials and flush pointing to the face of the brickwork wall.	p/m2	111.050	719.901	Seven Hundred and Nineteen point Nine Zero One	79945.006	Seventy-Nine Thousand Nine Hundred and Forty-Five point Zero Zero Six	I have seen
7	N/A	N/A	Extra over item 7 for the provision of sand cement plaster (1:4) to the faces of chamber flush pointing finish, all in accordance with Technical Specification and direction of Engineering in charge, and standard Details. The rate to include for the supply of all materials	p/m2	339.490	206.999	Two Hundred and Six point Nine Nine Nine	70274.091	Seventy Thousand Two Hundred and Seventy-Four point Zero Nine One	I have seen
8	N/A	N/A	Supplying, fitting and fixing steel grill fencing in boundary wall of any design and shape with 31 x 6 mm F.I. bar @ 150 mm c/c placed vertically after cutting as per required measurement. Welding the said F.I. bar with 2 Nos. horizontal 30 x 6 mm F.I. bar placed one at top and another at bottom including embedding/fixing the horizontal F.I. bar in position including cutting grooves in wall up to 150 mm depth and mending good the damages with C.C. (1:2:4) finished with two coats of painting with synthetic enamel paint over a coat of anti-corrosive paint etc. complete as per drawing and design and accepted by the Engineer.	p/m2	46.500	1869.901	One Thousand Eight Hundred and Sixty-Nine point Nine Zero One	86950.397	Eighty-Six Thousand Nine Hundred and Fifty point Three Nine Seven	I have seen
9	N/A	N/A	On exterior surface applying as per manufacturer instructions 3 coat of weather coat of approved quality and colour delivered from authorized local agent of the manufacturer in a sealed container complete in all respect in all floors and accepted by the Engineer.	p/m2	339.490	172.501	One Hundred and Seventy-Two point Five Zero One	58562.364	Fifty-Eight Thousand Five Hundred and Sixty-Two point Three Six Four	I have seen
							Grand Total:	496998.016	Four Lakh Ninety-Six Thousand	

