



স্মারক নং: 46.05.0000.509.31.152.23-1

Date: 28/05/2024

Tracking No :2024052821641603942

বরাবর,
নির্বাহী প্রকৌশলী
মডস জোন-৫
ঢাকা ওয়াসা।

বিষয়ঃ Raising, Cleaning of Air Release Valve, Washout line, Bulk Meter Chamber, Inter DMA Chamber at DMA-507 & 508 Under MODS Zone-5, Dhaka WASA . (Fy: 2023-24). কাজের সমাপ্তির বিল পরিশোধ প্রসঙ্গে।

Contract No : 46.05.0000.509.31.152.23-303
Work Order No : 46.05.0000.509.31.152.23-747

Date : 25/04/2024
Date : 25/04/2024

উপর্যুক্ত বিষয় ও সূত্রের প্রেক্ষিতে জানানো যাচ্ছে যে, Raising, Cleaning of Air Release Valve, Washout line, Bulk Meter Chamber, Inter DMA Chamber at DMA-507 & 508 Under MODS Zone-5, Dhaka WASA . (Fy: 2023-24). কাজটি দায়িত্ব প্রাপ্ত প্রকৌশলীগণের নির্দেশনা অনুযায়ী সুষ্ঠুভাবে গত 24/05/2024 ইং তারিখে 100% সম্পন্ন করেছি।

এমতাবস্থায়, উক্ত কাজের অনুকূলে পেমেন্ট ইনভয়েজ গ্রহণ করতঃ TK 4,55,803.000/- (Four Lakhs Fifty-Five Thousand Eight Hundred Three Taka Only) প্রদানের প্রয়োজনীয় ব্যবস্থা গ্রহণের জন্য অনুরোধ করছি।

নিবেদক,

28/05/2024 18:22:58 PM
Md. Takdir Hossain Swapan
Proprietor
M/S. A K International

Bill Application Information

Name of Cost Center:	MODS Zone-5
Name of Work:	Raising, Cleaning of Air Release Valve, Washout line, Bulk Meter Chamber, Inter DMA Chamber at DMA-507 & 508 Under MODS Zone-5, Dhaka WASA . (Fy: 2023-24).
Tender ID :	940604
Tender Method :	LTM EGP
Name of Firm :	M/S. A K International
Contract No :	46.05.0000.509.31.152.23-303
Work Order No :	46.05.0000.509.31.152.23-747
Contract Date :	25/04/2024
Work Order Date :	25/04/2024
Work End Date:	24/05/2024
Estimate Completion Date:	24/05/2024
Work Status :	100%
Mode of Bill :	1st Running Bill
Bill Amount :	4,55,803.000
Cost Center Head Name :	MOHAMMAD TAWHID ELAHI

Invoice No : 46.05.0000.509.31.152.23-1

Date: 28/05/2024

Payment Invoice

SL	Description	Quantity	Unit	Rate	Total
1	6" C class PVC pipe for fitting and fixing in SN and washout chamber, all M 50.29 931.001 Nin 46820.04 Fort completed as per direction of Engineer in charge,	50.29	m	931.00	46,820.040
2	Reinforced cement concrete works using wooden shutter, with minimum Cum cement content relates to mix ratio 1:2:4 having minimum fcr = 24 Mpa. and satisfying a specified compressive strength rc. 19 Mpa at 28 days on standard cylinders as per standard practice of Code ACI/BNBCIASTM & cement conforming to BDS EN-197-1- CEM 1, 52.5N (52.5MPa)/ ASTM-C 150 Type 7 I, best quality sand [50% quantity of best local sand (F.M. 1.2) and 50% quantity of Sythet sand or coarse sand of equivalent F.M. 2.2] and 20 mm down well graded picked jhama bnck chips conforming ASTM C-33 including breaking chips and screening, making, placing shutter in position and maintaining true to plumb. making shutter water-tight property, placing reinforcement in position; mixing in standard mixer machine with hoper fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering after specified time approved, including cost of water, electricity, additional testing charges of materials and cytlinders required by engineer. other charges etc. all complete approved and accepted by the Engineer.(Rate is excluding the cost of reinforcement and its fabrication, placing and binding etc;	22.32	Cum	8,673.00	193,581.382
3	Protection for safety - The site must be protected from all side by bamboo, P/Nos safety net & red tape. Traffic must be controlled during the work as per direction of the engineer-in-charge.	27	Per nos.	2,000.00	54,000.027
4	Skilled Manpower for earth excavation to rise SN Chamber,Washout Line,Bulk PNalves Meter Chamberinter DMA Chamber in Road level and back filling of sand washout operation as.per direction of the engineer-in-charge.	30	Each	1,500.00	45,000.030
5	Sand filling in foundation trenches and plinth with coarse sand having min F,M Cum t2 in 150mm in layers including leveling, watering and compaction o achieve minimum dry density of 90% with optimm moisture content (Modified proctor test) by raining each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the engineer.	81.74	Cum	1,167.00	95,390.662
6	Skilled technician for PVC pipe cutting, fitting and operating cutting disk es.per Each direction of the engineer-in-charge.	30	Each	1,500.00	45,000.030
				Total:	4,55,803.000
				Deduction 5 % less:	23,989.609
				Ground Total (Actual):	4,55,802.562
				Ground Total(Round):	4,55,803.000

In Words: Four Lakhs Fifty-Five Thousand Eight Hundred Three Taka Only.

Sincerely,

28/05/2024 18:22:58 PM
Md. Takdir Hossain Swapan
Proprietor
M/S. A K International

M/S. A K International
27, Noya Paltan (1st Floor) V I P Road, Dhaka-10000
Email: takdirhossain2727@gmail.com
Phone No: 01819240977

Bangladesh Electronic Fund Transfer Network (BEFTN)

Purpose Of Pay	Bank Name	Branch Name	Routing No	Account No	Type	Amount	Receiver Name	Mobile No
	UTTARA BANK LTD.	NORTH SHAHJAH ANPUR	250275085	145312200 211896	Current (CD) Account		M/S. A K International	01819240977

Sincerely,

28/05/2024 18:22:58 PM
Md. Takdir Hossain Swapan
Proprietor
M/S. A K International