



Dhaka Water Supply and Sewerage Authority


Office of the Executive Engineer


Padma Water Treatment Plant

Jashaldia, Louhajang, Munshiganj

Mobile: 01730-451702, E-mail: ee.pjwtp2019@gmail.com

Name of Work: Cleaning of sewer line at WTP unit.

Sl. No.	Description of Item	Rate Basis	Quantity	Unit	Rate (Tk/Unit)	Amount	Signature
01.	Removing sludge or semi-liquid clay/substances etc not suitable for pumping out or carrying by head load from the bottom of any marshy land, lake, ditch, pond by mixing fine local sand of F.M. 0.8 or less to a proportion such that it can be carried to an intermediate point of disposal and cutting the same including stacking and spreading properly on a suitable place to dry in the sun for a certain days and dispose the dried sludge or clay to a safe distance etc. complete and accepted by Engineer-in-charge subject to submit method statement to the engineer in charge for carrying out the works including ultimate disposal of the sludge under this item for approval. However, engineer's approval shall not relieve the Contractor of his responsibilities and obligations under the contract.	PWD rate schedule, Item 02.9	23.532	Cum	1054	24,802.728	
In Total (in figure)						24,802.728	
In Word: Twenty four thousand eight hundred and two point seven two eight taka only.							


20.03.2016

Gazi Asrib Bin Salam

Executive Engineer

Padma Water Treatment Plant

Dhaka WASA

