



DURDESH CONSTRUCTION

First Class Contractor & Supplier

Ref:

Date: ১৫.০৭.২০২৪



পেমেন্ট ইনভয়েস

বরাবর,

নির্বাহী প্রকৌশলী
ভান্ডার বিভাগ, ঢাকা ওয়াসা।

বিষয়: Repairing & maintenance of water line at Pagla Staff Quarters Compound, Dhaka WASA শীর্ষক কাজ প্রসঙ্গে।

জ্ঞাবহ,

সবিনয়ে বিবিত্ত নিবেদন এই যে, বিষয়োক্ত কাজটি আমি যথাযথভাবে সঠিক সময়ে স্পেসিফিকেশন মোতাবেক সুষ্ঠুভাবে সম্পাদন করেছি। সে অনুযায়ী আমাকে বিল প্রদান করার জন্য অনুরোধ করছি। নিম্নে বিল উপস্থাপন করা হ'ল।

বিষয় বর্ণিত কাজের বিলের বিস্তারিত বিবরণ:

ক্রঃ নং	কাজের বিস্তারিত বিবরণ	পরিমাণ	রেট	মোট টাকা
১	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract.	১.৮ বর্গমিটার	১৬৮/-	৩০২.৪
২	Cleaning and disposing of excavated earth from the construction site by truck or by any other means to a place within 30 km radius of the city or town area including loading & unloading at both ends, leveling and dressing the carried earth etc. complete and accepted by the Engineer-in-charge.	১.৮ বর্গমিটার	৭৫৬/-	১৩৬০.৮
৩	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	১.৮ বর্গমিটার	১২৯৬/-	২৩৩২.৮
৪	Supplying, fitting and fixing of best quality G.I. float valve, threaded joint Pit valve etc. complete approved and accepted by the Engineer-in-charge. 50 mm brass float valve	২টি	১৩১৬/-	২৬৩২/-
৫	Supplying, fitting and fixing of best quality G.I. gate valve with sealant etc. complete approved and accepted by the Engineer-in-charge. 50 mm brass gate valve	২টি	১৮৭৫/-	৩৭৫০/-
৬	Supplying, fitting and fixing of G.I. Union with sealant etc. complete in all respects approved and accepted by the Engineer-in-charge. 50 mm dia G.I. Union	২টি	৫২৬/-	১০৫২/-
৭	Supplying different inside dia best quality CPVC pressure pipe for water supply having specific gravity 1.35 - 1.45, and other physical, chemical, thermal, fire resistivity properties etc. as per BSI approved manufacturer standards or ASTM, BS/ISO/IS standards fitting and fixing in position with sockets, bends, with all accessories such as round grating/domed roof grating, bends, sockets etc. approved and accepted by the Engineer-in-charge (length: 6000 mm each). 50 mm dia wall thickness 3.9 mm - 4.5 mm	২০মিটার	৫৭১/-	১১৪২০/-
৮	Site Cleaning as per direction of the Engineer in charge.	১টি	১৭৫০/-	১৭৫০/-
				২৪,৬০০/-

মোট টাকা = চব্বিশ হাজার ছয়শত টাকা মাত্র।

জানতে পাই যে মোঃ হোসেন খান (নিবেদক)
 তারিখ: ১৫/০৭/২৪ মোঃ হোসেন খান
 মোঃ হোসেন খান (নিবেদক) মোঃ হোসেন খান
 মোঃ হোসেন খান (নিবেদক) মোঃ হোসেন খান
 মোঃ হোসেন খান (নিবেদক) মোঃ হোসেন খান
 Approved Tk. ২৪,৬০০/-



১৫/০৭/২৪
 মোঃ হোসেন খান
 নির্বাহী প্রকৌশলী

১৫/০৭/২৪
 মোঃ হোসেন খান
 নির্বাহী প্রকৌশলী

Durdesh Construction
 মোঃ মুনসুর হোসেন
 Proprietor